

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2125
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-129-10590-0000
API NUMBER

LEASE NAME Berryman Rickfield

WELL NUMBER Unit 25-2

688 Ft. from S Section Line

2000 Ft. from ^W Section Line

SEC. 16 TWP. 33S RGE. 41 (E) or (W)

COUNTY Morton

Date Well Completed 9-30-62

Plugging Commenced 7-20-95

Plugging Completed 7-26-95

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Tri Power Resources, Inc.

ADDRESS Box 849 Ardmore OK 73402

PHONE # (405) 226-6700 OPERATORS LICENSE NO. 07408

Character of Well OIL - ALUMPTA
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7-24-95 (date)

by Glen Barlow (KCC District Agent's Name).

Is ACO-1 filed? YES If not, Is well log attached? ---

Producing Formation MORROW Depth to Top 4830 Bottom 5030 T.D. 5125

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|---------------|------------|-------------|----------|--------------|--------|-------------|
| <u>MORROW</u> | <u>NIL</u> | <u>5124</u> | <u>0</u> | <u>4 1/2</u> | | <u>1527</u> |
| | | <u>1495</u> | <u>0</u> | <u>8 5/8</u> | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from feet to feet each s Mixed 1 SK hulls to 20 SK cmt. to plug perfs from 5030 to 4830. Mixed 50 SK cmt. plug from 1527 to 1377. Mixed 40 SK cmt. plug from 650 to 550. Mixed 10 SK plug from 33 to 3. Cut off & capped 8 5/8 3 ft. below ground level. Used mdd between plugs.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent And Horton Plugging, Inc. License No. 31151

Address Rt. 1, Box 49 BA Tyrone, OK 73951-9731

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: TRIPWIRE RESOURCES

STATE OF OKLAHOMA COUNTY OF CARROLL

W.B. CURRY JR. (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That, [I have knowledge of the fac statements, and matters herein contained and the log of the above-described well as filed : the same are true and correct, so help me God.

(Signature) W.B. Curry Jr.

(Address) PO Box 849 Ardmore, OK 73402

SUBSCRIBED AND SWORN TO before me this 14th day of August, 1995

Deani Allen
Notary Public

My Commission Expires: 11/10/97