

STATE OF KANSAS  
STATUTE CORPORATION COMMISSION  
130 S. Market, Room 2125  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-129-00149-0000  
API NUMBER

LEASE NAME Berryman Richfield

WELL NUMBER Unit 25-1

1750 Ft. from S Section Line

1063 Ft. from <sup>W</sup>/<sub>E</sub> Section Line

SEC. 16 TWP. 33S RGE. 41 (E) or (W)

COUNTY Morton

Date Well Completed 6-5-62

Plugging Commenced 7-26-95

Plugging Completed 8-1-95

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR TriPower Resources, Inc.

ADDRESS Box 849 Ardmore OK 73402

PHONE# (405) 276-6700 OPERATORS LICENSE NO. 03408

Character of Well OIL-NOW P+G

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7-26-95 (date)

by Glen Barlow (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached? \_\_\_\_\_

Producing Formation MORROW Depth to Top 4801 Bottom 5001 D. 5425

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>MORROW</u>	<u>NIL</u>	<u>5328</u>	<u>0</u>	<u>5 1/2</u>		<u>1534</u>
		<u>1467</u>	<u>0</u>	<u>8 5/8</u>		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each s Mixed 1 sk hulls & 25 sx cmt. to plug perfs from 5001 to 4801. Mixed 50 sx cmt. from 1534 to 1384. Mixed 40 sx cmt. from 650 to 550. Mixed 10 sx cmt. from 33 to 3. Cut off & cap 8 5/8 3 Ft. below ground level. Used mud between plugs.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent And Horton Plugging, Inc. License No. 31151

Address Rt. 1, Box 49 BA Tyrone, OK 73951-9731

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: TRIPOWER RESOURCES, INC.

STATE OF OKLAHOMA COUNTY OF CARTER, ss.

W. B. CURRY JR.

(Employee of Operator or Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the fac statements, and matters herein contained and the log of the above-described well, as filed i the same are true and correct, so help me God.

(Signature) W. B. Curry Jr.

(Address) P.O. Box 849 - Ardmore, OK 73402

SUBSCRIBED AND SWORN TO before me this 14th day of August, 1995

Deanie Allen  
Notary Public

My Commission Expires: 11/10/97