

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

175  
API NUMBER 15-174-20,654  
LEASE NAME Hitch Unit 0000

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1-11  
1400 Ft. from S Section Line  
1600 Ft. from E Section Line

LEASE OPERATOR Anadarko Petroleum Corporation  
ADDRESS P.O. Box 351, Liberal, KS 67905-0351  
PHONE#(316) 624-6253 OPERATORS LICENSE NO. 4549

SEC. 3 TWP. 33SRGE. 34 (R) or (W)  
COUNTY Seward

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed 10-15-82  
Plugging Commenced 2-7-94  
Plugging Completed 2-11-94

The plugging proposal was approved on 2-2-94 (date)  
by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? previously submitted

Producing Formation L. Chester Depth to Top 6164 Bottom 6178 T.D. 6320

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	1628	0
				5 1/2	6319	1210

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from    feet to    feet each set.  
Pump 1 sk hulls & 25 sxs cmt 6178-5980. Shot csg 1210. Pumped 60 sxs cmt 1210-1050. Pump 60 sxs 650-550. Id 29 jts 5 1/2 csg (1210 ft). Pump 10 sxs cmt 40-0. Cut off & cap 3' below ground level. Restore location. State Rep - Glenn Barlow.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent & Horton Plugging Service License No. 31151

Address Rt 1 Box 49BA, Tyrone, Oklahoma 73951-9731

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation


STATE OF Kansas COUNTY OF Seward, ss.

Beverly J. Williams, Technical Assistant (Employee of Operator) or Operator of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Beverly J. Williams  
(Address) Beverly J. Williams, Tech. Asst.  
P.O. Box 351, Liberal, KS 67905-0351

SUBSCRIBED AND SWORN TO before me this 8th day of March 1994

My Commission Expires:



Notary Public

STATE CORPORATION COMMISSION  
RECEIVED  
MARCH 10 1994  
3-10-94  
CONSERVATION FORM CP-4  
Wichita, Kansas  
Revised 05/78