

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 28 2003

WELL PLUGGING RECORD
K.A.R.-62-3-117

API NUMBER 15-189-00022-0000

LEASE NAME Carpenter

WELL NUMBER 1-26

1980 Ft. from N Section Line

1980 Ft. from W Section Line

SEC. 26 TWP. 33 RGE. 37W (E) or (W)

COUNTY Stevens

Date Well Completed 05/14/60

Plugging Commenced 08/14/03

Plugging Completed 08/14/03

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

CONSERVATION DIVISION
LEASE OPERATOR Chesapeake Operating, Inc.
ADDRESS P. O. Box 18496, Oklahoma City, OK 73154-0496
PHONE (409) 848-8000 OPERATORS LICENSE NO. 32334

Character of Well Gas
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 05/14/02 (date)
by David Williams (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Morrow Depth to Top 6142' Bottom 6156' T.D. 6663'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8-5/8" | 2862' | |
| | | | | 5-1/2" | 6229' | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. MIRU Log-Tech, set CIBP @6109' w/2 sx cmt on top, RIH w/2nd CIBP @1880', load 5-1/2" casing, test to 500#, perf @1850', pump 400 sx 60/40 cmt w/6% gel & circ up backside of 8-5/8", max PSI 500#, SIP 0#, RDMQ, State man Jim Holland on location

Name of Plugging Contractor Allied Cementing Co., Inc. License No. _____

Address P. O. Box 31, Russell, KS 67665 (785)483-2626

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Chesapeake Operating, Inc.


STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Jim Reisch (Employee of Operator) or (Operator) o
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts
statements, and matters herein contained and the log of the above-described well as filed the
the same are true and correct, so help me God.

(Signature) Barbara J. Bale for Jim Reisch
Jim Reisch

(Address) P.O. Box 18496, Okla. City, OK 73154-0496

SUBSCRIBED AND SWORN TO before me this 27th day of August, 2003



Commission Expires: 11/27/04

Lucretia A. Morris #00218352
Notary Public