

15-189-00431-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
Finney State Office Building

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER _____ NA (COMPLETED 1940) _____

LEASE NAME CRAWFORD "A"

130 South Market, Rm 2078
Wichita, Kansas 67202

RECEIVED
KANSAS STATE CORPORATION COMMISSION
NOTICE: TYPE OR PRINT
Fill out completely
and return to Cons. Div.
office within 30 days

WELL NUMBER 1

~~4980~~ 3300 Ft. from ~~3~~ Section Line

~~4980~~ 2310 Ft. from E Section Line

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

SEC. 30 TWP. 33S RGE. 37 (E) or (W)

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

COUNTY STEVENS

PHONE # (316) 624-6253 OPERATORS LICENSE NO. 4549

Date Well Completed 1940

Character of Well GAS

Plugging Commenced 09/25/97

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 09/29/97

The plugging proposal was approved on 09/16/97 (date)

by MR. GARY WINTERS (KCC District Agent's Name)

Is AC0-1 filed? YES If not, is well log attached? _____

Producing Formation CHASE Depth to Top 2546' Bottom 2812' T.D. 2812'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
CHASE	GAS	2546'	2812'	8-5/8"	559'	3'
				5-1/2"	2546'	500'

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set. MIRU PLUGGERS, PMPG 3 SXS HULLS & 40 SXS CMT TO PLUG 2346-2546', LD HOLE W/MUD, SHOT CSG OFF @ 500', CIRC MUD & SPOT 70 SXS CMT TO PLG FROM 500-350', LD 17 JTS 7" CSG, SPOT 15 SXS CMT TO PLG FROM 40-0', CUT OFF & CAP 3' BELOW GL, INSCRIBE CAP, RESTORE LOCATION, WITNESSED BY KCC REP GARY WINTERS.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT & HORTON PLUGGING, INC. License No. 31151

Address RT. 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE: (405) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, SS.

JOHN A. BROMAN, DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John A. Broman
JOHN A. BROMAN, DIVISION PRODUCTION ENGINEER

(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 4th day of November, 1997

Shirley J. Childers
Notary Public

My Commission Expires: 11/14/98

