

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Stevens County, Sec. 32 Twp. 33S Rge. 37W (E) (W)

Location as "NE/CNWxSWx" or footage from lines C NE

Lease Owner Panhandle Eastern Pipe Line Company

Lease Name Crawford Well No. 1-32

Office Address Box 828, Liberal, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Gas

Date well completed 8-6 19 30

Application for plugging filed 2-5 19 65

Application for plugging approved 19 65

Plugging commenced 2-15 19 65

Plugging completed 2-18 19 65

Reason for abandonment of well or producing formation Replaced

If a producing well is abandoned, date of last production December 19 64

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 2780 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FRDM	TO	SIZE	PUT IN	PULLED OUT
				12-1/2	569	
				8-5/8	2607	908
				4-1/2	2116	2028

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Pumped 125 sxs. into 8-5/8" casing. Pumped 115 sxs. cement at 650' and 9 sxs. at 10'.

STATE CORPORATION COMMISSION

MAR 2 1965

3-2-65

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sargent's Casing Pulling Service

Address 1546 Clay Court, Liberal, Kansas

STATE OF KANSAS COUNTY OF SEWARD ss.  
J. P. Phillippe, Supt. Drlg. & Prod. (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. P. Phillippe Supt. Drlg. & Prod.  
Box 828, Liberal, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of February, 19 65

Ronald L. Harrison  
Notary Public.

My commission expires \_\_\_\_\_

My Commission Expires Sept. 29, 1968

15-189-00433-0000

PANHANDLE EASTERN PIPE LINE CO.

Well Name: Crawford #1-32

Company: Panhandle Eastern Pipe Line Co.

Location: Center NE $\frac{1}{2}$ -32-33-37

Drilling Contractor: R. E. Andres

County: Stevens

Date Commenced: 6-15-30

Orig. Open Flow: 4,000 MCF

Date Completed: 8-6-30

Orig. Rock: 430#

Elevation: 3129'

30 Surface Clay  
 90 Sand  
 260 Clay and gyp  
 460 Sand  
 572 Clay gravel and sand. Set 569' of 12 $\frac{1}{2}$ " surface cemented with 100 sacks.  
 1013 Clay gravel and shells.  
 1043 Red bed  
 1220 Hard gyp  
 1670 Hard gyp and red bed  
 1682 Red bed  
 1739 Hard gyp  
 1901 Hard lime  
 1914 Anhydrite  
 2018 Hard gyp and red bed  
 2035 Anhydrite  
 2119 Hard gyp  
 2127 Red bed  
 2134 Hard lime  
 2193 Lime and red bed  
 2235 Red bed, streaks lime and anhydrite  
 2244 Anhydrite  
 2316 Hard gyp  
 2334 Anhydrite  
 2354 Broken lime  
 2386 Anhydrite  
 2408 Broken lime  
 2426 Anhydrite  
 2490 Broken lime  
 2500 Hard shale  
 2533 Broken lime  
 2539 Hard lime  
 2540 Gyp  
 2564 Broken lime  
 2578 Hard lime  
 2580m Lime. Set 2607' of 8 $\frac{1}{4}$ " casing.  
 2620 Lime  
 2630 Sand small show of gas  
 2675 Lime  
 2732 Sandy lime  
 2750 Red rock  
 2760 Sand  
 2770 More gas from sandy lime  
 2780 Big gas  
 2780 TOTAL DEPTH

RECEIVED  
STATE CORPORATION COMMISSION

APR 26 1965

CONSERVATION DIVISION  
Wichita, Kansas