

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
Finney State Office Building  
130 South Market, Rm 2078  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-189-224270000

LEASE NAME CRAWFORD "D"

WELL NUMBER 5

2304 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 32 TWP. 33S RGE. 37 (E) or (W)

COUNTY STEVENS

Date Well Completed 01-10-2003

Plugging Commenced 01-10-2003

Plugging Completed 01-11-2003

RECEIVED

FEB 03 2003

KCC WICHITA

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS 701 S. TAYLOR ST., SUITE 400, AMARILLO, TX 79101

PHONE # ( 806 ) 457-4600 OPERATORS LICENSE NO. 4549

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 01-10-2003 (date)

by MR. RICHARD LACEY (KCC District Agent's Name).

Is AC0-1 filed? YES If not, is well log attached? \_\_\_\_\_

Producing Formation NONE Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 6700'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	1753'	NONE

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set. TIH W/4-1/2" DP TO 3200'. SPOT 100 SXS 60/40 POZ W/6%GEL @ 3200. TOH TO 1780' & SPOT 50 SXS. TOH TO 700' & SPOT 40 SXS. TOH TO 40' & SPOT 10 SXS AT 0-40'. SPOT 15 SXS IN RH & 10 SXS IN MH. CUT OFF 8-5/8" CSG 3' BELOW GI AND CAP. PERMANENTLY INSCRIBE WELL NAME, NUMBER AND DATE PLUGGED ON CAP.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor HALLIBURTON ENERGY SERVICES License No. 5287

Address P. O. BOX 1598, LIBERAL, KANSAS 67905-1598

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF TEXAS COUNTY OF POTTER, ss.

L. MARC HARVEY, ENGINEERING TECHNICIAN III (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) L. Marc Harvey

L. MARC HARVEY, ENGINEERING TECHNICIAN III  
(Address) 701 S. TAYLOR, SUITE 400, AMARILLO, TX 79101



SUBSCRIBED AND SWORN TO before me this 29 day of January, 2003

Lori Pearson  
Notary Public

My Commission Expires: 2/26/05