


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Seward County. Sec. 11 Twp. 34 Rge. 32 (E) (W)
Location as "NE/CNW&SW" or footage from lines C SE NW
Lease Owner Anadarko Production Company
Lease Name Lynn "A"
Office Address Box 351 Liberal, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 21 19 64
Application for plugging filed September 21 19 64
Application for plugging approved 19
Plugging commenced September 21 19 64
Plugging completed September 21 19 64
Reason for abandonment of well or producing formation Dry



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott
Producing formation Depth to top Bottom Total Depth of Well 6468 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	1581	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.
Filled hole with mud to 700' and spotted 35 sxs. cement; spotted 15 sxs. at 45'.

RECEIVED
STATE CORPORATION COMMISSION

SEP 24 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Moran Bros., Inc.
Address 1200 Oil & Gas Bldg., Wichita Falls, Texas

STATE OF KANSAS, COUNTY OF SEWARD, ss.
S. H. Neithercoat (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) S. H. Neithercoat
Box 351 Liberal, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of September, 19 64
Donald L. Carpenter Notary Public.

My commission expires

DRILLER'S LOG

WELL NAME Lynn "A" #1 COMPANY OPERATING Anadarko Production Company
 ADDRESS of COMPANY Box 351, Liberal, Kansas
 WELL LOCATION C 1/4 SE 1/4 NW 1/4,
660 ft. North of South line,
1980 ft. East of West line; Sec. 11 Twp. 34 Rge. 32, Seward County, Kansas
 DRILLING STARTED 9-2, 1964 DRILLING COMPLETED 9-21, 1964
 WELL COMPLETED 9-21, 1964 WELL CONNECTED _____, 19____
 ELEVATION 2742.37 ft. Ground Level CHARACTER OF WELL (Oil, Gas, or Dry Hole) Dry Hole

OIL OR GAS SANDS OR ZONES - PERFORATIONS - ACIDIZING AND FRACTURING INFORMATION					
Name	From	To	No. of Shots	Gallons Used	Kind Used

CASING RECORD

Size	Amount Set	Sacks of Cement	Amount Pulled
8-5/8	1581	850	None

FORMATION RECORD

Formation	Top	Bottom	Formation	Top	Bottom
Surface sand and clay	0	700	Total Depth	6468	
Sand, red bed & gypsum	700	1284			
Red bed & anhydrite	1284	2306			
Anhydrite & shale	2306	2364			
Lime & shale	2364	2952			
Lime	2952	4205			
Lime & shale	4205	4550			
Lime	4550	5862			
Lime & shale	5862	5947			
Lime & sand	5947	6070			
Lime	6070	6245			
Lime & sand	6245	6332			
Lime	6332	6468			

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 24 1964
 CONSERVATION DIVISION
 Wichita, Kansas

RESULTS of INITIAL PRODUCTION TEST: _____