


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Seward County. Sec. 10 Twp. 34S Rge. (E) 32(W)

Location as "NE/CNW/SE" or footage from lines. C SE NW
Lease Owner Anadarko Production Company
Lease Name Reimer "C" Well No. 1
Office Address Box 351, Liberal, Kansas 67901
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed December 22 19 68
Application for plugging filed (verbal) December 22 19 68
Application for plugging approved (verbal approval) December 22 19 68
Plugging commenced December 23 19 68
Plugging completed December 23 19 68
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ed Eves, Sublette, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 6466 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole filled with mud.
Spotted 35 sacks of cement from 800' - 900'.
Filled hole with mud to 45'.
Spotted 15 sacks of cement from 45' to surface.
Completed @ 10:45 a.m. December 23, 1968.

RECEIVED
STATE CORPORATION COMMISSION
DEC 31 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lohmann-Johnson Drilling Company
Address 1737 Wichita Plaza Bldg., Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEWARD, ss.
V. K. Downey (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

V. K. Downey
Superintendent
Liberal Production Region

(Signature) [Signature]
P.O. Box 351, Liberal, Kansas 67901
(Address)

Subscribed and sworn to before me this 27th day of December, 19 68

[Signature]
Notary Public.



DRILLER'S LOG

WELL NAME: Reimer "C" No. 1 ; COMPANY OPERATING: Anadarko Production Company
 ADDRESS of COMPANY: Box 351 Liberal, Kansas 67901

WELL LOCATION: C 1/4 SE 1/4 NW 1/4,
3315 ft. North of South line,
 ft. East of West line: Sec. 10, Twp. 34S, Rge. 32W, Seward County, Kansas

DRILLING STARTED 12-1, 1968; DRILLING COMPLETED 12-22, 1968
 WELL COMPLETED , 19 ; WELL CONNECTED , 19

ELEVATION: 2761.5 ft. Ground Level; CHARACTER OF WELL (Oil, Gas, or Dry Hole) Dry hole

OIL OR GAS SANDS OR ZONES - PERFORATIONS - ACIDIZING AND FRACTURING INFORMATION					
Name	From	To	No. of Shots	Gallons Used	Kind Used

CASING RECORD

Size	Amount Set	Sacks of Cement	Amount Pulled
8 5/8	1577	725	

FORMATION RECORD

Formation	Top	Bottom	Formation	Top	Bottom
Sand & Shells	0'	1994'			
Shale	1994'	2577'			
Shale & Lime	2577'	2934'			
Lime	2934'	3153'			
Lime & Shale	3153'	3535'			
Lime	3535'	3904'			
Lime & Shale	3904'	4076'			
Lime	4076'	5583'			
Lime & Shale	5583'	5951'			
Lime	5951'	6466'			
T.D.	6466'				

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 31 1968
 CONSERVATION DIVISION
 Wichita, Kansas

RESULTS of INITIAL PRODUCTION TEST: P & A 12-23-68