

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-175-21257-0000

LEASE NAME Pittman

WELL NUMBER #1

2310 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 10 TWP. 34 SRGE. 32W (E) or (W)

COUNTY Seward

Date Well Completed _____

Plugging Commenced 5/25/94

Plugging Completed 5/25/94

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Charter Production Company

ADDRESS 142 N. Mosley, Wichita, KS 67202

PHONE# (316) 263-4906 OPERATORS LICENSE NO. 30444

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5/25/94 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		surface	1529'	8 5/8"	35 jts	none
				5 1/2"	35 jts	35 jts

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.
See Attached

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor J. W. Gibson Well Service Co. License No. 5866

Address Box 1383, Guymon, OK 73942-1383

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Charter Production Company

STATE OF Kansas COUNTY OF Sedgwick, ss.


Jerald Rains

(Employee of Operator) or _____

above-described well, being first duly sworn on oath, says: That I have knowledge of _____ statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jerald Rains

(Address) 142 N. Mosley
Wichita, KS 67202



before me this 1st day of June, 1994

Nancy Kandt
Notary Public

My Commission Expires: 2-4-96

RECEIVED
STATE CORPORATION COMMISSION

JUN 03 1994

CONSERVATION DIVISION
Wichita, Kansas

**CHARTER PRODUCTION COMPANY
142 NORTH MOSLEY
WICHITA, KANSAS 67202
316-263-4906**

**PITTMAN #1-1992 HPEP
NW NW SW
SECTION 10-34S-32W
SEWARD COUNTY, KANSAS
OBERON PROSPECT**

PLUGGING REPORT

5-23-94 MIRU Well Service Unit.
5-24-94 POH with 79 7/8" rods, 104 3/4" rods, pump and 149 joints 2 7/8" tubing.
5-25-94 Ran gauge ring to 4500'. FL 3400'. Set CIBP at 4485' and dump-bailed 2 sxs cement.
Worked casing and found casing free at 1700'. Cut casing at 1580' and spotted 50 sxs
cement plug at 1560'. Pulled casing to 700' and spotted 40 sxs cement plug. Pulled
casing to 40' and spotted 10 sxs cement plug. Pulled 35 joints 5 1/2" casing. Plugged
& abandoned. Plugging orders from Glenn Barlow, KCC.

FINAL REPORT

RECEIVED
STATE COMMISSION
JUN 03 1994
CONSERVATION DIVISION
Wichita, Kansas



CEMENT BOND LOG

API# 15-175-21257

COMPANY CHARTER PRODUCTION COMPANY WELL PITTMAN #1 FIELD WILDCAT CNTY SEWARD STATE KS	COMPANY CHARTER PRODUCTION COMPANY	WELL FILE
	WELL <u>PITTMAN #1</u>	
	FIELD <u>WILDCAT</u>	
	COUNTY <u>SEWARD</u> STATE <u>KANSAS</u>	
LOCATION: NW - NW - SW 2310 FSL - 4950 FEL SEC. <u>10</u> TWP. <u>34 S</u> RGE. <u>32 W</u>		OTHER SERVICES: PERFORATE

PERM. DATUM <u>GROUND LEVEL</u> ELEV. <u>2767</u> LOG MEASURED FROM <u>K.B. 11</u> FT. ABOVE PERMANENT DATUM DRILLING MEASURED FROM <u>KELLY BUSHING</u>	ELEV.: K.B. <u>2778</u> D.F. <u>----</u> G.L. <u>2767</u>
--	---

DATE	7-31-92
RUN NO.	ONE
DEPTH DRILLER	6480
DEPTH LOGGER	5151
BTM. LOG INTERVAL	5144
TOP LOG INTERVAL	3700
OPEN HOLE SIZE	7 7/8
TYPE FLUID	WATER
DENS.	VISC.
MAX. REC. TEMP. °F	
EST. CEMENT TOP	3850
TIME WELL READY	0830
TIME LOGGER ON BTM.	0900
EQUIP. NO.	#702
LOCATION	LIBERAL, KS.
RECORDED BY	TOLLEFSON
WITNESSED BY	MR. MOOREHEAD

BOREHOLE RECORD				TUBING RECORD			
RUN NO.	BIT	FROM	TO	SIZE	WGT.	FROM	TO

CASING RECORD	SIZE	WT/FT	GRADE	TYPE JOINT	TOP	BOTTOM
SURFACE STRING	8 5/8				SURF.	1516
PROD. STRING	5 1/2				SURF.	T.D.
LINER						

RECEIVED
 STATE CORPORATION COMMISSION
MAY 09 1994
 CONSERVATION DIVISION
 Wichita, Kansas