


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Seward County, Sec. 7 Twp. 34 Rge. 32 (E) (W)  
Location as "NE/CNW/SW" or footage from lines C NW SE  
Lease Owner Anadarko Production Company  
Lease Name Condit "A" Well No. 1  
Office Address P. O. Box 351, Liberal, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed November 14 1962  
Application for plugging filed November 14 1962  
Application for plugging approved 19  
Plugging commenced November 14 1962  
Plugging completed November 14 1962  
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh E. Scott  
Producing formation None Depth to top Bottom Total Depth of Well 6420 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
None				8 5/8"	1627	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.  
Spotted 50 sacks cement @ 1800', spotted 35 sacks @ 700', spotted 15 sacks @ 45' to surface.

NOV 19 1962  
15-175-10141-0000  
STATE CORPORATION COMMISSION  
Conservation Division  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor: Midwestern Drillers  
Address: 1206 Mid-Continent Building, Tulsa 3, Oklahoma

STATE OF KANSAS, COUNTY OF SEWARD, ss.  
S. H. Neithercoat (employee of owner) or ~~owner or operator~~ of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) S. H. Neithercoat

P. O. Box 351, Liberal, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of November, 1962

My Commission Expires July 24, 1965  
My commission expires \_\_\_\_\_

Mary Beth Gray  
Mary Beth Gray  
Notary Public.

DRILLER'S LOG

WELL NAME Condit "A" COMPANY OPERATING Anadarko Production Company  
 ADDRESS of COMPANY Box 351, Liberal, Kansas

WELL LOCATION C 1/2 NW 1/2 SE 1/2,  
1980 ft. North of South line,  
1980 ft. ~~East~~ of ~~West~~ line; Sec. 7 Twp. 34 Rge. 32, Seward County, Kansas  
 West East

DRILLING STARTED October 26, 19 62 DRILLING COMPLETED November 14, 19 62  
 WELL COMPLETED November 14, 19 62 WELL CONNECTED \_\_\_\_\_, 19 \_\_\_\_\_

ELEVATION 2824.12 ft. Ground Level CHARACTER OF WELL (Oil, Gas, or Dry Hole) Dry Hole

OIL OR GAS SANDS OR ZONES - PERFORATIONS - ACIDIZING AND FRACTURING INFORMATION					
Name	From	To	No. of Shots	Gallons Used	Kind Used
None					

CASING RECORD

Size	Amount Set	Sacks of Cement	Amount Pulled
8 5/8"	1627'	900	None

FORMATION RECORD

Formation	Top	Bottom	Formation	Top	Bottom
Surface Sand	0	280	Lime & Shale	5520	6015
Surface Sand & Shale	280	700	Lime	6015	6030
Red Bed & Gypsum	700	1605	Lime & Shale	6030	6290
Anhydrite	1605	1630	Lime	6290	6360
Anhydrite & Red Bed	1630	2570	Lime & Shale	6360	6415
Anhydrite & Shale	2570	2715	Lime	6415	6420
Shale & Lime	2715	4543	Total Depth	6420	
Lime	4543	4600			
Lime & Shale	4600	5060			
Lime	5060	5180			
Lime & Shale	5180	5279			
Lime	5279	5520			

RESULTS of INITIAL PRODUCTION TEST: None

**RECEIVED**  
 STATE CORPORATION COMMISSION

NOV 19 1962  
 CONSERVATION DIVISION  
 Wichita, Kansas