

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER NA
LEASE NAME CONDIT "A"
WELL NUMBER 2
SPOT LOCATION C SW SW
SEC. 7 TWP. 34 SRGE. 32 (E) or (W)
COUNTY Seward
Date Well Completed 12/14/64
Plugging Commenced 12/6/83
Plugging Completed 12/8/83

See file

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Anadarko Production Company
ADDRESS P. O. Box 351, Liberal, Kansas 67901

PHONE # (316) 624-6253 OPERATORS LICENSE NO. 5469

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District #1 office

Is ACO-1 filed? No If not, is well log attached? Drillers Log attached

Producing formation Morrow Depth to top 5956' bottom 5962' T.D. 6383'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Chester	Oil	6236	6240	8-5/8"	1615	0
L. Morrow	Oil	6074	6077	4-1/2"	6382	2800
Morrow	Oil	5956	5962			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Spot 20 sx cmt from 5962' to 5750'; filled hole with mud. Shot 4-1/2" csg off @ 2800'; Spot 50 sx cmt from 1650' to 1555'; spot 40 sx cmt from 800' to 700'; spot 10 sx cmt from 40' to 3'; cut off casing 3' below GL and capped well; hole was filled with mud at all times.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargents Casing Pulling Service License No. 6547
Address 620 South Lincoln, Liberal, Kansas 67901

STATE OF KANSAS COUNTY OF SEWARD, ss.

Paul Campbell (employee of operator) or
~~operator~~ of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.

RECEIVED
STATE CORPORATION COMMISSION

(Signature) Paul Campbell
(Address) P. O. Box 351, Liberal, KS 67901

APR 02 1984

SUBSCRIBED AND SWORN TO before me this 30th day of March, 1984

CONSERVATION DIVISION
Wichita, Kansas
My Commission expires November 21, 1986

Beverly J. Williams
Notary Public

BEVERLY J. WILLIAMS
Seward County, Kansas
My Comm. Exp. 11/21/86

DRILLER'S LOG

WELL NAME: Condite "A" No. 2; COMPANY OPERATING: Amadarko Production Company
 ADDRESS of COMPANY: Box 351, Liberal, Kansas

WELL LOCATION: C 1/4 SW 1/4 SW 1/4,
660 ft. North of South line,
660 ft. East of West line; Sec. 7, Twp. 34S, Rge. 32W, Seward County, Kansas

DRILLING STARTED 11-12, 1964; DRILLING COMPLETED 12-3, 1964
 WELL COMPLETED 12-14, 1964; WELL CONNECTED _____, 19____

ELEVATION: 2024.02 ft. Ground Level; CHARACTER OF WELL (Oil, Gas, or Dry Hole) Oil

OIL OR GAS SANDS OR ZONES - PERFORATIONS - ACIDIZING AND FRACTURING INFORMATION					
Name	From	To	No. of Shots	Gallons Used	Kind Used
Lower Chester	6235	6240	16	225	10% HCl acid
				10,000	Gelled diesel

CASING RECORD

Size	Amount Set	Sacks of Cement	Amount Pulled
8-5/8"	1015'	670	
4-1/2"	632'	185	

FORMATION RECORD

Formation	Top	Bottom	Formation	Top	Bottom
Surface from to gravel	0	204			
Red bed to sand	204	317			
Red bed, sand to conglomerate	317	1539			
Red bed to sand	1539	1615			
conglomerate to lime	1615	1720			
conglomerate to red bed	1720	2197			
lime to sand	2197	2429			
lime	2429	2763			
lime to sand	2763	6303			
Total depth	6303				

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 05 1963
 CONSERVATION DIVISION
 Wichita, Kansas

RESULTS of INITIAL PRODUCTION TEST: Flowed 249 Ebls. oil in 7 hours + 734 MCFD of gas.

DRILLER'S LOG

WELL NAME: Condit "A" No. 2 ; COMPANY OPERATING: Araderko Production Company
 ADDRESS of COMPANY: Box 351, Liberal, Kansas

WELL LOCATION: C 1/4 NW 1/4 SW 1/4,
660 ft. North of South line,
660 ft. East of West line; Sec. 7, Twp. 34S, Rge. 32W, Seward County, Kansas

DRILLING STARTED 11-12, 1964; DRILLING COMPLETED 12-3, 1964
 WELL COMPLETED 12-14, 1964; WELL CONNECTED _____, 19____

ELEVATION: 2824.02 ft. Ground Level; CHARACTER OF WELL (Oil, Gas, or Dry Hole) Oil

OIL OR GAS SANDS OR ZONES - PERFORATIONS - ACIDIZING AND FRACTURING INFORMATION					
Name	From	To	No. of Shots	Gallons Used	Kind Used
<u>Lower Chester</u>	<u>6236</u>	<u>6240</u>	<u>16</u>	<u>225</u>	<u>10% HCl acid</u>
				<u>10,000</u>	<u>Gelled diesel</u>

CASING RECORD

Size	Amount Set	Sacks of Cement	Amount Pulled
<u>6-5/8"</u>	<u>1615'</u>	<u>650</u>	
<u>4-1/2"</u>	<u>632'</u>	<u>185</u>	

FORMATION RECORD

Formation	Top	Bottom	Formation	Top	Bottom
<u>Surface sand & gravel</u>	<u>0</u>	<u>20'</u>			
<u>Red bed & sand</u>	<u>20'</u>	<u>917</u>			
<u>Red bed, sand & anhydrite</u>	<u>917</u>	<u>1599</u>			
<u>Red bed & sand</u>	<u>1599</u>	<u>1616</u>			
<u>Anhydrite & lime</u>	<u>1616</u>	<u>1700</u>			
<u>Anhydrite & red bed</u>	<u>1700</u>	<u>2195</u>			
<u>Sand & lime</u>	<u>2195</u>	<u>2429</u>			
<u>Lime</u>	<u>2429</u>	<u>2563</u>			
<u>Sand & lime</u>	<u>2563</u>	<u>6323</u>			
<u>Total Depth</u>	<u>6323</u>				

RECEIVED
 STATE CORPORATION COMMISSION
 APR 02 1984
 CONSERVATION DIVISION
 Wichita, Kansas

RESULTS of INITIAL PRODUCTION TEST: Flowed 249 Ebls. oil in 7 hours + 734 MCFD of gas.