

STATE OF KANSAS
STATE CORPORATION COMMISSION
Finney State Office Building
130 South Market, Rm 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-175-21765 - 0000

LEASE NAME ALEXANDER "C"

WELL NUMBER 2

4030 Ft. from S Section Line

4030 Ft. from E Section Line

SEC. 4 TWP. 34 RGE 32 (E) or (W)

COUNTY SEWARD

Date Well Completed 1-4-1999

Plugging Commenced 2-1-1999

Plugging Completed 2-1-1999

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-29-1999 (date)

by MR. STEVE MIDDLETON (KCC District Agent's Name)

Is ACO-1 filed? YES If not, is well log attached?

Producing Formation NONE Depth to Top Bottom T.D. 3320

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	523	NONE
				5-1/2"	3310'	614'

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set. MIRU. TIH W/BAILER & SPOT 2 SXS CMT ON TOP OF CIBP @ 3000'. TOH. MIX & PUMP 3 SXS HULLS & 50 SXS 60/40 POZ CMT W/6% GEL TO PLUG PERES @ 2616-2662' (OA). TIH & SPOT 25 SXS CMT @ 1600'. TOH. PULL FREE POINT & CUT OFF 5-1/2" @ 614'. TOH W/5-1/2 CSG TO 570'. PMP 50 SXS CMT FROM 570-470'. TOH TO 50' & PMP 10 SXS CMT 40' TO SURFACE. TOH W/REMAINING 5-1/2" CSG. CUT OFF AND CAP 8-5/8" 3' BELOW GL. PERMANENTLY INSCRIBE WELL NAME, NUMBER AND DATE PLUGGED ON CAP. RDMO. RESTORE LOCATION.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor HALLIBURTON ENERGY SERVICES License No. 5287

Address P.O. BOX 1598, LIBERAL, KANSAS 67905-1598

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.

L. MARC HARVEY, DRILLING TECHNICAL ASSISTANT (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) L. Marc Harvey 2-5-99

L. MARC HARVEY DRILLING TECHNICAL ASSISTANT
(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 5th day of February, 1999.

FREDA L. HENZ
Notary Public - State of Kansas
My Appt. Expires 5-15-99

Notary Public