

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
280 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER NA

LEASE NAME CONDIT UNIT

WELL NUMBER 7-1

3300 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 19 TWP. 34S RGE. 32 (E) or (W)

COUNTY Seward

Date Well Completed 5/4/65

Plugging Commenced 2/5/88

Plugging Completed 2/10/88

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P. O. Box 351, Liberal, Kansas 67905

PHONE# (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well water injector

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12/17/87 (date)

by Shari Feist (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? Drillers log Filed w/Form CP-1

Producing Formation L. Chester Depth to Top 6279 Bottom 6292 T.D. 6400

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>L. Chester</u>	<u>Oil</u>	<u>Surf</u>	<u>1600</u>	<u>8-5/8</u>	<u>1600</u>	<u>0</u>
		<u>Surf</u>	<u>6399</u>	<u>4-1/2</u>	<u>6399</u>	<u>2830</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.  
Rigged up Sargents. Pmpd 25 sxs cmt and 2 sxs hulls 6291-6050, cut off 4-1/2 csg @ 2830.  
Pmpd 50 sxs cmt 1650-1550, pmpd 25 sxs cmt 700-600, pmpd 10 sxs cmt 40-0. Cut off and capped 8-5/8 csg 3' below ground level.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargents Casing Pulling Service License No. 6547

Address 620 South Lincoln, Liberal, Kansas 67901


STATE OF KANSAS COUNTY OF SEWARD, ss.

M. L Pease, Production Manager (Employee of Operator) or ~~XXXXXXX~~ of above-described well, first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

MAY 19 1988

(Signature) M. L Pease

(Address) P. O. Box 351, Liberal, KS 67905



AND SWORN TO before me this 18<sup>th</sup> day of May, 19 88  
Beverly J. Williams  
Notary Public  
November 21, 1990

DRILLER'S LOG

WELL NAME: Etzenhouser "A" ; COMPANY OPERATING: Annabelle Production Company  
 ADDRESS of COMPANY: Box 351, Liberal, Kansas  
 WELL LOCATION: C 1/4 SW 1/4 NE 1/4,  
3435 ft. North of South line,  
600 ft. East of West line; Sec. 19, Twp. 34N, Rge. 32W, Sevier County, Kansas  
 DRILLING STARTED 4-11, 1965; DRILLING COMPLETED 4-23, 1965  
 WELL COMPLETED 5-4, 1965; WELL CONNECTED \_\_\_\_\_, 19\_\_\_\_  
 ELEVATION: 2911 ft. Ground Level; CHARACTER OF WELL (Oil, Gas, or Dry Hole) Oil

OIL OR GAS SANDS OR ZONES - PERFORATIONS - ACIDIZING AND FRACTURING INFORMATION					
Name	From	To	No. of Shots	Gallons Used	Kind Used
Mississippi	6284	6292	16	500	MCA

CASING RECORD

Size	Amount Set	Sacks of Cement	Amount Pulled
8-5/8"	1600	900	None
4-1/2"	6399	125	None
2-3/8"	6305	-	-

FORMATION RECORD

Formation	Top	Bottom	Formation	Top	Bottom
Surface Sand & Clay	0	812			
Red Bed & Sand	812	1370			
Red Bed & Anhydrite	1370	1601			
Red Bed & Gypsum	1601	2599			
Lime & Sand	2599	3038			
Lime & Sand	3038	3905			
Lime & Sand	3905	4492			
Lime	4492	5515			
Lime & Sand	5515	6266			
Lime & Sand	6266	6400			
Total Depth	6400				

RESULTS of INITIAL PRODUCTION TEST: Swabbed & Floved 52.17 bbls. oil in 6 hours (Gravity 41.5