

STATE OF KANSAS
STATE CORPORATION COMMISSION
Finney State Office Building
30 South Market, Rm 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-175-20476 00-01

LEASE NAME DODD

WELL NUMBER B-2

1980 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 18 TWP. 34S RGE 32 (X) or (W)

COUNTY SEWARD

Date Well Completed 9-10-1980

Plugging Commenced 3-29-2003

Plugging Completed 4-2-2003

RECEIVED
APR 09 2003
KCC WICHITA

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS 701 S TAYLOR, STE 400 AMARILLO, TX 79101

PHONE # (806) 457-4600 OPERATORS LICENSE NO. 4549

Character of Well _____

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3-23-2003 (date)

by RICHARD LACEY (KCC District Agent's Name).

Is AC0-1 filed? YES If not, is well log attached? _____

Producing Formation KANSAS CITY, MARMATON Depth to Top 5004 Bottom 5192 T.D. 6405

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
KANSAS CITY	DRY	5004	5008	8 5/8	1572	0
MARMATON	DRY	5178	5192	5-1/2	6404	2211

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. PLUG PERFS W/ 400# HULLS AND 25 SXS CMT. SHOOT 5-1/2 CSG AT 2211. SPOT 50 SXS CMT FROM 1600 TO 1450. SPOT 50 SXS CMT FROM 550 TO 300. SPOT 10 SXS FROM 30 TO 3. CUT OFF AND CAP 8-5/8 CSG 3 BELOW GL.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address RT 1 BOX 49BA, TYRONE, OK 73951-9731 PHONE: (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF TEXAS COUNTY OF POTTER, ss.
CRAIG R. WALTERS, P.E., DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Craig R. Walters
CRAIG R. WALTERS, P.E., DIV. PROD. ENGINEER

(Address) 701 S. TAYLOR, STE 400 AMARILLO, TX 79101



SUBSCRIBED AND SWORN TO before me this 7 day of April, 2003

Lori Pearson
Notary Public

My Commission Expires: 2/26/05