

(October 1990)

UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT

SUBMIT IN DUPLICATE

(See other instructions on reverse side)

FOR APPROVED OMB NO. 1004-0137 Expires: December 31, 1991

3. LEASE DESIGNATION AND SERIAL NO.

KS NM 67927

8. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT AGREEMENT NAME

8. FARM OR LEASE NAME, WELL NO.

USA "AD" No. 1

9. API WELL NO.

15-129-211410000

10. FIELD AND POOL, OR WILDCAT

Stirrup

11. SEC., T., R., M., OR BLOCK AND SURVEY OR AREA

Sec. 11-33S-40W

12. COUNTY OR

Morton

13. STATE

Kansas

RECEIVED DEC 03 1992

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. TYPE OF WELL: OIL WELL [X] GAS WELL [ ] DRY [ ] Other [ ]

b. TYPE OF COMPLETION: NEW WELL [X] WORK OVER [ ] DEEP-EN [ ] PLUG BACK [ ] DIFF. CONVR. [ ] Other [ ]

2. NAME OF OPERATOR: Anadarko Petroleum Corporation

3. ADDRESS AND TELEPHONE NO.: P. O. Box 351, Liberal, Kansas 67905-0351 (316) 624-6253

4. LOCATION OF WELL: At surface 1980' FSL & 660' FWL of Sec. 11-33S 40W. At top prod. interval reported below Same. At total depth Same.

14. PERMIT NO. 15-129-211410000 DATE ISSUED 9-25-92

15. DATE SPUDDED 10-2-92 16. DATE T.D. REACHED 10-15-92 17. DATE COMPL. (Ready to prod.) 11-16-92 18. ELEVATIONS (DF, BKB, RT, GR, ETC.)\* 3275.6 GR 19. ELEV. CASINGHEAD NA

20. TOTAL DEPTH, MD & TVD 5760 21. PLUG BACK T.D., MD & TVD 5489 22. IF MULTIPLE COMPL., HOW MANY? NA 23. INTERVALS DRILLED BY ROTARY TOOLS X CABLE TOOLS

24. PRODUCING INTERVAL(S), OF THIS COMPLETION—TOP, BOTTOM, NAME (MD AND TVD)\* 5392-5412 (morrow) 25. WAS DIRECTIONAL SURVEY MADE Yes

26. TYPE ELECTRIC AND OTHER LOGS RUN DIL/SFL/GR; CNL/LDT/GR; Microlog 27. WAS WELL CORED No

28. CASING RECORD (Report all strings set in well)

Table with 6 columns: CASING SIZE/GRADE, WEIGHT, LB./FT., DEPTH SET (MD), HOLE SIZE, TOP OF CEMENT, CEMENTING RECORD, AMOUNT PULLED. Rows include 8 5/8, 5 1/2, and FO Tool.

29. LINER RECORD

Table with 8 columns: SIZE, TOP (MD), BOTTOM (MD), SACKS CEMENT, SCREEN (MD), SIZE, DEPTH SET (MD), PACKER SET (MD). Row shows None for size and NA for packer set.

31. PERFORATION RECORD (Interval, size and number)

5408-5412 4 SPF Tot Shots = 16
5392-5408 4 SPF Tot Shots = 64

32. ACID, SHOT, FRACTURE, CEMENT SQUEEZE, ETC.

Table with 2 columns: DEPTH INTERVAL (MD), AMOUNT AND KIND OF MATERIAL USED. Rows include 5392-5412 with HCL Acid and 5392-5412 with x-linked gelled 2% KCL wtr.

33. PRODUCTION

DATE FIRST PRODUCTION 11-16-92 PRODUCTION METHOD Pumping WELL STATUS Producing

DATE OF TEST 11-16-92 HOURS TESTED 24 CHOKE SIZE NA PROD'N. FOR TEST PERIOD 184 OIL-BBL. 44 WATER-BBL. 28 GAS-OIL RATIO

FLOW, TUBING PRESS. 34 CASING PRESSURE 31 CALCULATED 24-HOUR RATE 184 OIL-BBL. 44 WATER-BBL. 28 OIL GRAVITY (API GRV.) 35.4

34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.) Sold TEST WITNESSED BY 3 1993

35. LIST OF ATTACHMENTS: KCC ACO-1, Drillers Log, Electric Logs, Cement Tickets.

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records

SIGNED Beverly J. Williams TITLE Engineering Technician DATE 11-30-92

(See Instructions and Spaces for Additional Data on Reverse Side)

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

Kansas Corporation Commission

RECEIVED NOV 30 1992 CONSERVATION DIVISION WICHITA, KANSAS

37. SUMMARY OF POROUS ZONES: (Show all important zones of porosity and contents thereof; cored intervals; and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries):

38.

GEOLOGIC MARKERS

FORMATION	TOP	BOTTOM	DESCRIPTION, CONTENTS, ETC.	NAME	TOP	
					MEAS. DEPTH	TRUE VERT. DEPTH
B/Stone Corral	1583					
Chase	2301					
Council Grove	2603					
Admire	2842					
Wabaunsee	3030					
Topeka	3274					
Haebner	3777					
Toronto	3792					
Lansing	3892					
Kansas City	4295					
Marmaton	4584					
Cherokee	4778					
Morrow	5206					
"D" Sand	5388					
L. Morrow	5517					
Keyes	5650					
Chester	5710					
St. Genevieve	5737					
TD	5760					
				Sand & Redbed	0	1189
				Glorietta Sand	1190	1300
				Redbed	1301	2780
				Lime-Shale	2781	5760