

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

BLM-TULSA D.O.

15-129-10372-0000  
CORP

FORM APPROVED  
Budget Bureau No. 1004-0135  
Expires: March 31, 1993

**SUNDRY NOTICES AND REPORTS ON WELLS**

JUL 18 5 53 AM '94

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.  
Use "APPLICATION FOR PERMIT—" for such proposals

5. Lease Designation and Serial No.

KS NM 67961

6. If Indian, Allottee or Tribe Name

7. If Unit or CA, Agreement Designation

NM 041A2087C1120

8. Well Name and No.  
SCOTT 1-18

9. API Well No.  
6/21/55 <sup>15-129-10372-00-00</sup> SPUD DATE

10. Field and Pool, or Exploratory Area  
GREENWOOD

11. County or Parish, State  
MORTON

**SUBMIT IN TRIPLICATE**

1. Type of Well

Oil Well  Gas Well  Other

2. Name of Operator

ANADARKO PETROLEUM CORPORATION

3. Address and Telephone No.

P. O. BOX 351, LIBERAL, KANSAS 67905-0351 (316) 624-6253

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

1320' FSL & 1320' FWL SECTION 18-34S-42W

12. CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

TYPE OF ACTION

- Notice of Intent
- Subsequent Report
- Final Abandonment Notice

- Abandonment
- Recompletion
- Plugging Back
- Casing Repair
- Altering Casing
- Other

- Change of Plans
- New Construction
- Non-Routine Fracturing
- Water Shut-Off
- Conversion to Injection
- Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)\*

NOTICE OF INTENT TO PLUG & ABANDON A SHUT-IN PRODUCING WELL. \*

ORIGINAL COMPLETION DATE : 6/30/55

ANTICIPATED PLUGGING DATE: UPON KCC APPROVAL.

PLUGGING METHOD: MIX AND PUMP 15 SXS CMT PLUG FROM 2500-2595'. DISPLACE w/61 BBLS 9 PPG MUD. MIRU SARGENTS CASING PULLERS. PULL ON 5 1/2" CSG, LOCATE FREE POINT AND SHOOT OFF. SPOT 35 SXS CMT PLUG AT CUT OFF POINT. PULL 5 1/2" CSG TO 448'. SPOT 35 SXS CMT PLUG FROM 448' -548'. TOH W 5 1/2" CSG AND SPOT 15 SXS CMT PLUG FROM 53'-3'. CUT OFF 8 5/8" CSG 3' BELOW GROUND LEVEL AND CAP. INSCRIBE WELL NAME AND NUMBER, LEGAL DESCRIPTION AND PLUGGING DATE ON CAP. RDMO CASING PULLERS AND RESTORE LOCATION.

\*REPLACED BY THE USA AF-1 REDRILL.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 09 1994  
CONSERVATION DIVISION  
WICHITA, KANSAS

14. I hereby certify that the foregoing is true and correct

Signed Daniel Kappeler

Title DIVISION PRODUCTION MANAGER <sup>Engineer</sup>

Date 7/12/94

(This space for Federal or State office use)

Approved by (ORIG. SGD.) VIRGIL L. PAULI

Title CHIEF, BRANCH OF FLUID OPERATIONS

Date JUL 25 1994

Conditions of approval, if any:

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

Kansas Corporation Commission

\*See Instruction on Reverse Side