

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

WELL PLUGGING RECORD

Seward County, Sec. 16 Twp. 34 Rge. 32 (W)

Location as "NE/CNW<sup>1</sup>/<sub>4</sub>SW<sup>1</sup>/<sub>4</sub>" or footage from lines Gen. SE/4

Lease Owner Lario Oil & Gas Company

Lease Name Pennington Well No. 1

Office Address 301 South Market, Wichita, Kansas

Character of Well (completed as ~~Oil Gas or~~ Dry Hole)

Date well completed November 7, 19 56

Application for plugging filed (Verbal 11-7-56) November 9, 19 56

Application for plugging approved (Verbal 11-7-56) November 9, 19 56

Plugging commenced November 7, 19 56

Plugging completed November 7, 19 56

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Pratt, Kansas

Producing formation Depth to top Bottom Total Depth of Well 6118 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	1544'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

50 sacks of cement at 5977' through drill pipe.  
25 sacks cement at 2550' through drill pipe.  
35 sacks cement on top of plug set at 600' through drill pipe.  
12 sacks of cement on top of plug set at 35' to bottom of cellar.  
All cement pumped in by Halliburton Oil Well Cementing Co.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 17 1956  
CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Co.  
Address Sterling, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.  
Leo Ross (employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Leo Ross*

301 S. Market, Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 16th day of November, 19 56

*Frances Leslie*  
Notary Public.

My commission expires July 21, 1958

23-8390-s 6-51-20M  
PLUGGING  
FILE SEC 16 T 34 R 32W  
BOOK PAGE 114 LINE 39

LARIO OIL & GAS COMPANY  
 No. 1 Pennington  
 Cen. SE/4 Sec. 16-34S-32W  
 Seward County, Kansas

Date Commenced: October 3, 1956  
 Date Completed: November 7, 1956  
 Drilling Contractor - Sterling Drilling Co.  
 Total Depth - 6118'  
 I.P. - Dry and Abandoned

Casing Records:  
 8 5/8" 1544' Set @ 1533'  
 Cem. 100 sacks

Formation	Depth	Geological Tops - Rotary Bushing Meas.	
		Elevation	
Gravel	400	2768 DF	2770 RB
Clay, sand	650	2635	/ 134
Red bed and sand	1135	2658	/ 112
Red bed	1522	2684	/ 86
Anhydrite	1565	2752	/ 18
Shale	1665	2805	- 36
Anhydrite & shale	2117	4316	-1546
Shale	2204	4378	-1608
Shale & lime	2420	4511	-1741
Anhydrite streaks & shale	2470	5184	-2414
Lime & chert streaks	2550	5398	-2628
Dolomite chert	2626	5767	-2997
Chert & lime	2693	5816-23	-3046 - 53
Sand & chert streaks	2751	5852-60	-3082 - 90
Dolomite, shale	2851	5925-50	-3155 - 80
Dolomite & sand	2928	5967-77	-3197 - 3207
Dolomite & shale	2970	Chester	5982 -3212
Dolomite & lime	3119	Rotary Total Depth	6118 -3348
Lime	3385	Schlumberger T.D.	6118 -3348
Lime & shaly lime	3435		
Shaly lime	3590		
Lime	3725		
Lime & shale	3775		
Shale	3790		
Shale & lime	3859		
Shale	4364		
Shale & lime	4400		
Lime	4534		
Chert stks. & lime	4602		
Lime	4742		
Chert & lime	4784		
Lime	5166		
Lime & shale	5204		
Lime	5330		
Lime & shale	5357		
Lime	5463		
Lime & shale	5494		
Shale	5580		
Lime & shale	5650		
Shale & lime stks.	5789		
Shale	5815		
Shale & sand	5825		
Core #1	5827-5845		
Shale	5857		
Shale & lime	5867		
Shale	5930		
Core #2 - Sand	5930-5977		
Shale & sand	5989		
Lime	6118 T.D.		

\*\*\*\*\*

I hereby certify that this is a true and correct log of the above mentioned well.

*Leo Ross*  
 Leo Ross

STATE OF KANSAS )  
 ) ss  
 COUNTY OF SEDGWICK )

Subscribed and sworn to before me, a notary public in and for said County and State, this 16th day of November, 1956.

*Frances Leslie*  
 Notary Public

My Commission expires July 21, 1958.

RECEIVED  
 STATE COMMISSION  
 CONSERVATION DIVISION  
 WICHITA, KANSAS

PLUGGING  
 SEC 16, T. 34, R. 32W  
 BOOK PAGE 114, LINE 39