


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Seward County, Sec. 16 Twp. 34S Rge. 32W E/W
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines
NE SW SW

Lease Owner Inca Oil Company
Lease Name Pennington Well No. 1
Office Address Box 1578 Liberal, Kansas 67901
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole



Locate well correctly on above
Section Plot

Date Well completed 19
Application for plugging filed 11-8 1979
Application for plugging approved 11-10 1979
Plugging commenced 11-12 1979
Plugging completed 11-14 1979
Reason for abandonment of well or producing formation
dry hole

If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas
Producing formation Depth to top Bottom Total Depth of Well 6350
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|-------|--------|------------|
| | | | | 8 5/8 | 1497 | none |
| | | | | 4 1/2 | 6347 | 2650 |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

Pump 20 sks. of cement @ 5208 to 5000

Pump 40 sks. of cement @ 1500 to 1400

Put 10 sks. of cement @ 40 to 0

RECEIVED
STATE CORPORATION COMMISSION

NOV 29 1979

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sargents Casing Pulling Ser. Box 506 Liberal, Kansas Ks. No. 511

STATE OF Kansas COUNTY OF Seward, ss.
Ned E. Lowry (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Ned E. Lowry, Agent
P. O. Box 1578, Liberal, Kansas 67901
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of November, 1979

My commission expires



Bettie Hutchinson
Notary Public.

15-175-20160-0000

KANSAS DRILLERS LOG


IMPORTANT
Kans. Geo. Survey request
samples on this well.

S. 16 T. 34 R. 32 W

Loc. NE SW SW

County Seward

API No. 15 — 175 — 20,160-A WASHDOWN
County Number



Locate well correctly
Elev.: Gr. _____

DF _____ KB _____

Operator
Inca Oil Corp.

Address
P. O. Box 1578 Liberal, Kansas 67901

Well No. #1 Lease Name Pennington

Footage Location
990 feet from ~~XX~~ (S) line 990 feet from ~~XX~~ (W) line

Principal Contractor DaMac Drilling Company Geologist _____

Spud Date 10-6-79 Total Depth 6423' P.B.T.D. 6000' CIBP

Date Completed 10-31-79 Oil Purchaser _____

CASING RECORD

Report of all strings set— surface, intermediate, production, etc.

| Purpose of string | Size hole drilled | Size casing set (in O.D.) | Weight lbs/ft. | Setting depth | Type cement | Sacks | Type and percent additives |
|-------------------|-------------------|---------------------------|----------------|---------------|--------------|-------|-----------------------------|
| surface | 12 1/2" | 8 5/8" | | 1497' | | | |
| production | 7 7/8" | 4 1/2" | 10.5# | 6347' | class H | 50 | 8% gel, 12 1/2# gilsonite |
| | | | | | 50/50 pozmix | 320 | 10% salt, .08% Halad9 |
| | | | | | | | 18% salt, 12 1/2# gilsonite |
| | | | | | | | .08% Halad9 |

LINER RECORD

PERFORATION RECORD

| Top, ft. | Bottom, ft. | Sacks cement | Shots per ft. | Size & type | Depth interval |
|----------|-------------|--------------|---------------|---------------|----------------|
| | | | 1 | 3 1/8" gun DP | 6020-6092 |
| | | | 2 | 3 1/8" gun DP | 5200-5208 |

TUBING RECORD

| Size | Setting depth | Packer set at |
|------|---------------|---------------|
| | | |

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

| Amount and kind of material used | Depth interval treated |
|--|------------------------|
| 94,500 scf CO ₂ ; 12 bbls 15% NE acid w/37,800 scf CO ₂ ; 12 bbls water w/37,800 scf CO ₂ | 6020-6092 |
| 200 gal 20% HRTA-1 acid w/2000 gal CO ₂ | 6020-6092 |
| 300 gal 15% NE acid | |

STATE RECEIVED
5200-5208
CONSERVATION COMMISSION

INITIAL PRODUCTION

Date of first production _____ Producing method (flowing, pumping, gas lift, etc.) _____

RATE OF PRODUCTION PER 24 HOURS
Oil _____ Gas _____ Water _____
bbls. MCF bbls. Kansas CFPB

Disposition of gas (vented, used on lease or sold) _____ Producing interval(s) _____

NOV 25 1979

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator
Inca Oil Corporation

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:
Dry Hole

Well No. 1

Lease Name
Pennington

S 16 T 34S R 32W E
W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

| FORMATION DESCRIPTION, CONTENTS, ETC. | TOP | BOTTOM | NAME | DEPTH |
|--|-----|--------|------|-------|
| (information not available - washdown) | | | | |

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Jimmy Lee Barlow
Signature

Agent/ Inca Oil Corporation
Title

November 8, 1979
Date