
15-191-01556-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Sumner County. Sec. 16 Twp. 30 Rge. 1 (E) (W)
Location as "NE/CNW¼SW¼" or footage from lines SW NW NW
Lease Owner Fred Nixon
Lease Name Bell Well No. 1
Office Address 405 First Nat'l. Bank Bldg. - Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed August 15 1959
Application for plugging filed August 15 1959
Application for plugging approved August 15 1959
Plugging commenced August 15 1959
Plugging completed August 15 1959
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well Lee Guthrie
Producing formation Depth to top Bottom Total Depth of Well 3537 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, CAS OR WATER RECORDS — CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	350'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole filled with heavy rotary mud to 360 ft. Wooden plug at 360 ft. with 15 sacks cement on plug. Hole filled with heavy rotary mud to 35 ft. Wooden plug at 35 ft. with 10 sacks cement on plug. Rat hole filled with mud & capped with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
DEC 14 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor White & Ellis Drilling, Inc.
Address Box 448 - El Dorado, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.
Dale R. Daniel, employee of contractor (~~employee of owner~~) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dale R. Daniel
Box 448 - El Dorado, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of August, 19 59

Emery Sifford
Notary Public.

My commission expires May 21, 1960

5441

15-191-01556-0000

Casing Record

8 5/8 — 350 Cemented w/225 sacks

Location: SW NW NW
Section: 16-30-1W
Sumner County, Kansas
Farm: Bell #1
Well Owner: Fred Nixon
Contractor: White & Ellis Drilling
Started: 8-5-59
Completed: 8-15-59

T.D. 3537'

Kelly Busing measurement 5' above ground level.

FORMATION	DEPTH
Soil	0-20
Shale & Lime	50
Shale & Lime stks.	165
Shale & Salt stks.	315
Anthydrite	385
Lime	840
Lime & Shale stks.	910
Shale & Lime stks.	1040
Shale	1170
Lime & Shale stks.	1340
Lime & Shale	1400
Shale & Shells	1550
Lime & Shale	1610
Shale & Lime	1970
Lime & Shale	2150
Shale & Lime	2315
Lime & Shale stks.	2421
Shale & Lime	2580
Sand & sdy. Shale	2640
Sand	2680
Shale	2883
Lime	3120
Shale & Lime stks.	3195
Shale & Lime	3402
Lime	3415
Shale & Lime	3487
Lime	3537

TOPS

Kansas City	2883
Base Kansas City	3097
Mississippi	3487

Dry hole
Plugged & abandoned

RECEIVED
STATE CORPORATION COMMISSION
DEC 14 1959
CONSERVATION DIVISION
Wichita, Kansas