

Q

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Sumner County, Sec. 15 Twp. 30 Rge. 1 (E) (W) X

Location as "NE/CNW/SW" or footage from lines SE NW NE
Lease Owner Petroleum Management Inc.
Lease Name Chitwood Well No. #3
Office Address Box 922, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 4-20-71 19
Application for plugging approved 19
Plugging commenced 5-4-71 19
Plugging completed 5-5-71 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well Howard Hess
Producing formation Depth to top Bottom Total Depth of Well 3898' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	3896'	2566.26'
				10 3/4"	350'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Made bottom hole plug back with sand to 3500'. Mixed and ran 5 sacks cement thru dump bailer.
Bailed hole down to 315' - set 15' rock bridge. Filled hole with 6 yards ready-mix to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
MAY 7 1971
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Southwest Casing Pulling Co.
Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Southwest Casing Pulling Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer, Sr.
Box 364, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 6 day of May, 1971

MILLER SYDNEY J. PUBLIC NOTARY
212 MARKET WICHITA, KANSAS
My commission expires 24 October 1972

Sidney J. Miller
Notary Public.

15-191-01139-0000

WELL RECORD

Thomas W. Sullivan Et Al
CHITWOOD WELL NO. 3
Drilling Com. 5-27-51 Rotary
Drilling Comp. 7-11-51 Rotary
Drilling Contractor - H. M. Williams

Sec. 15, T. 30s, R. 1w
SE NW NE
SUMNER COUNTY, KANSAS
Elevation 1259 D.F.

Casing:

10" 350' (300 sk. cement)
5 1/2" 3896' (150 sk. cement)

FIGURES INDICATE BOTTOM OF FORMATIONS.

Soil	40	
Shale & Shells	310	
Anhydrite	360	
Lime & Shale	710	
Lime	770	
Lime & Shale	990	
Sandy Lime & Shale	1085	
Lime & Shale	2143	
Lime	2200	
Lime & Shale	2550	
Sandy Shale	2570	
Lime & Shale	2703	
Shale	2730	
Sandy Shale	2770	
Shale	2775	
Lime & Shale	2950	
Sand & Shale	2965	
Lime & Shale	3215	
Shale	3235	
Lime & Shale	3667	
Lime	3676	
Lime & Shale	3775	
Lime, Sandy	3803	
Shale & Lime	3896	Top Simpson Sand
Simpson Sand	3898	
Total Depth with Rotary	3898	

RECEIVED
STATE CORPORATION COMMISSION
APR 21 1971
CONSERVATION DIVISION
Wichita, Kansas