

15-191-10172-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Sumner County. Sec. 15 Twp. 30 Rge. 1 (E) W (W)
Location as "NE/CNW/SW" or footage from lines NW/NE/SE
Lease Owner Woodmen Tennitt Drilling Co.
Lease Name Snyder Well No. A3
Office Address Box 387 Holsington, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed _____ 19____
Application for plugging filed May 5, 1965
Application for plugging approved May 8, 1965
Plugging commenced May 7, 1965
Plugging completed May 10, 1965
Reason for abandonment of well or producing formation No longer a producer.

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Howard Hess
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3885 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	325'	None
				5 1/2	3874'	2752'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back with sand from 3885' to 3860'. Mixed and dumped 4 sx. of cement from 3860' to 3828'. Pulled casing. Mudded hole to 220'. Set 20' rock bridge from 220' to 200' / Dumped 2 1/2 yds. of ready mixed cement from 200' to base of the cellar.

RECEIVED
STATE CORPORATION COMMISSION

MAY 28 1965

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Ace Pipe Pulling Co.
Address Box 304 Great Bend, Ka.

STATE OF Kansas, COUNTY OF Barton, ss.
William D. Hoberecht (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) William D. Hoberecht

Box 304 Great Bend, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of May, 1965

My commission expires March 1, 1966

Shelby V. Maier
Notary Public.

15-191-10172-0000

Woodman-Iann

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

COPY


15-30-1W

Company- M. J. SULLIVAN et al
Farm- Snyder "A" No. 3

SEC. 15 T. 30 R. 1W
NW NE SE

Total Depth. 3885
Comm. 11-18-50 Comp. 12-10-50
Shot or Treated.
Contractor. H. M. Williams
Issued. 4-18-53

County Sumner
KANSAS



CASING:
10" 293' cem w/275 sx
5 1/2" 3877'

Elevation. 1249

Production. Initial pmg Pot. 356
bbls & no water

Figures indicate Bottom of Formations.

soil, shale, shells	75
shale, lime	260
anhydrite	295
shale, lime	300
shale, shells	900
shale, lime	1225
lime	1350
lime sandy	1415
shale, shells	1740
lime, shale	2602
shale sandy	2622
sand	2672
shale	2690
shale, lime	2830
shale	2858
lime	3018
lime, shale	3250
shale	3335
lime, shale	3395
shale	3455
lime, shale	3481
lime	3570
lime, shale	3594
lime	3827
shale	3877
sand, Simpson	3885
Total Depth	RTD

Tops:	
Stalnaker Sand	2500
Kansas City Lime	2835
Marmaton-Cherokee	3090
Miss. lime	3460
Kinderhook	3720
Simpson	3860

RECEIVED
STATE CORPORATION COMMISSION
MAY 28 1965
CONSERVATION DIVISION
Wichita, Kansas