

15-191-01470-0000

REC'D JUN 27 1958

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Sumner County. Sec. 14 Twp. 30 Rge. 1 (E) W (W)

Location as "NE/CNW%SW%" or footage from lines SE NE NE
Lease Owner Brunson Drilling Co., Inc.
Lease Name Clara Williams #1 Well No.
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 6-18-58 19
Plugging completed 6-24-58 19
Reason for abandonment of well or producing formation

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eugene Graham
Producing formation Depth to top Bottom Total Depth of Well 3863 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	374'	none
				5-1/2"	3859'	3408'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked the hole to 3863' and found it open.
Filled w/sand to 3840' and ran 5 sacks of cement. Pulled 5 1/2" casing. Cleared hole and bailed oil and mud to 240', set a 10' rock bridge and ran 15 sacks of cement. Mudded the hole to 20', set a rock bridge and ran 5 sacks of cement to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Co., Inc.
Address Chase, Kansas

STATE OF KANSAS COUNTY OF RICE, ss.
Ralph B M Laughlin (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ralph B M Laughlin
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of June, 19 58

My commission expires 9-27-58

Thomas V. [Signature] Notary Public.
STATE CORPORATION COMMISSION

PLUGGING
FILE SEC 14 T. 30 R. 1W
BOOK PAGE 107 LINE 39

JUL 1 - 1958
CONSERVATION DIVISION
Wichita, Kansas

BRUNSON-SPINES
Wichita, Kansas

WELL: WILLIAMS #1
COMMENCED RD: 5-13-58
COMPLETED RD: 5-27-58
TOTAL DEPTH: 3862'
CASING: 377' 8-5/8"

SE NE NE
14-30S-1W
SUMNER COUNTY, KANSAS
ELEVATION: 1235 RB
CONTRACTOR: Brunson-Spines

STRATA	DEPTH	TOPS
Clay	30	Miss. Limestone 3423 (-2188)
Sand	60	Kinderhook 3793 (-2558)
Shale & Shells	205	Simpson Sand 3858 (-2623)
Anhydrite & Shale	305	
Anhydrite	400	
Lime	555	
Lime & Shale	650	
Sandy Lime	690	
Lime & Shale	2560	
Shale & Sand	2640	
Shale & Lime	2855	
Lime	3160	
Lime & Shale	3292	
Lime	3862	
Total Depth	3862	

D & A

I hereby certify that the above is a true and correct log of said well as reflected by the daily drilling report.

BRUNSON-SPINES

Ralph B. McLaughlin
Ralph B. McLaughlin

Signed and sworn to in my presence this 12th day of June, 1958, by Ralph B. McLaughlin, Secretary-Treasurer of Brunson-Spines.

Mary G. LaFollette
Mary G. LaFollette, Notary Public

My commission expires June 16, 1959

PLUGGING
FILE SEC. 14 T. 30 R. 1W
BOOK PAGE 107 LINE 39

RECEIVED
STAT. CORPORATION COMMISSION
JUL 1 - 1958
CONSERVATION DIVISION
Wichita, Kansas