

15-191-01466-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD


OR
FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging of formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Sumner County. Sec. 30 Twp. 30 Rge. (E) 1 (W)
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. C NE SW
Lease Owner. Richmond & Reigle
Lease Name. Stunkel Well No. 1
Office Address. 501 State Street, Augusta, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed. March 9, 1944
Application for plugging filed. July 18, 1944
Application for plugging approved. July 18, 1944
Plugging commenced. July 26, 1944
Plugging completed. July 31, 1944
Reason for abandonment of well or producing formation.

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production. 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well. W. G. Buffington
Producing formation. Depth to top. Bottom. Total Depth of Well. 3885 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				10"	177'	
				5 $\frac{1}{2}$ "	3835'	2248'4"
Well Log attached						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Total depth 3885'. Pipe set at 3835'. Mud from bottom to bottom of pipe. Mud to 177' 10' rock bridge, 10 sacks of cement, mud to 10' of top. 5 sacks of cement on 10-foot rock bridge. Filled to surface.

PLUGGING
FILE # 13 30RLW
BOOK PAGE 124 LINE 33



(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Richmond & Reigle
Address. 501 State Street, Augusta, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.
C. S. Richmond ~~employee or owner~~ (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. S. Richmond
501 State Street, Augusta, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 5th day of August, 1944
M. E. Black
Notary Public.

My commission expires October 10, 1946

DRILLER'S LOG

RICHMOND & REIGLE
Stunkel Well No. 1

Sec. 13 T 30 R 1W
C NE SW

Total Depth with Rotary 3835'
Cable Tools drilled 3835' to 3885'
Rotary Tools comm. 2-15-1944
Rotary Tools comp. 3- 9-1944
Contractor (rotary) H. M. Williams Drilling Co.
Contractor (cable) J. S. McKnab


SUMNER County

Production
DRY

CASING
10" 177'
5 1/2" 3834'

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand & shale	180	
lime	205	
lime & shale	365	
lime	515	
lime & shale	635	
lime	745	
lime & shale	1035	
shale & shells	1385	
lime & shale	1910	
lime	1985	
lime & shale	2040	
lime	2150	
lime & shale	2245	
lime	2390	Top Kansas City
lime & shale	2841	2841
lime	3020	Cored 2947-59
lime & shale	3025	
lime	3045	
lime & shale	3167	
lime	3191	
lime & shale	3430	Top Mississippi
lime	3515	Lime 3430
lime & shale	3561	
lime	3598	
shale	3675	
lime & shale	3785	
lime	3805	Top Black Shale
black shale	3835	3805
black shale & sand	3861	
lime & sand	3883	
Sandy lime, hard and white	3885	
Total depth		



Water 3880 to 3883
Sulphur water at 3883
HFV 3883 to 3885

PLUGGING
 FILE 13 30 1W
 BOOK PAGE 124 12-33