

15-129-00158-0001

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 2/89

**WELL PLUGGING APPLICATION FORM**  
(File One Copy)  
Not Assigned

API NUMBER Completed 1962 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Merrico Resources, Inc. OPERATOR'S LICENSE NO. 03408 5-92

ADDRESS P.O. Box 849, Ardmore, Ok. 73402 PHONE # (405) 226-6700

LEASE (FARM) Berryman Richfield Unit 22-1 WELL NO. 22-1 WELL LOCATION SE NW COUNTY Morton

SEC. 9 TWP. 33S RGE. 41 (E) or (W) TOTAL DEPTH 5450 PLUG BACK TD 5293

**Check One:**

OIL WELL  GAS WELL  D & A  SWD or INJ WELL  DOCKET NO. E-18039

SURFACE CASING SIZE 8-5/8" SET AT 1490' CEMENTED WITH 625 SACKS

CASING SIZE 5-1/2" SET AT 5330' CEMENTED WITH 175 SACKS

PERFORATED AT 5026-5030

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Set CIBP over existing perms W/20' cement on top. Shoot pipe at free point & pull to bottom of surface pipe & pump 50sx cement through csg., if csg is good. If not, run 2-3/8" to cement with. Pump 35 sx cement at 700'. Pull out of  
(If additional space is needed use back of form.) (SEE REVERSE)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Unknown  
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Upon Commission Approval

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

David Releford PHONE # (316) 592-4321

ADDRESS P.O. Box 484, Elkhart, Ks. 67950

PLUGGING CONTRACTOR Sargents Casing Pullers LICENSE NO. 6547 6-92

ADDRESS P.O. Box 506, Liberal, KS. 67905-0506 PHONE # (316) 624-7455

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: W.B. Curry, Jr.  
(Operator or Agent) W.B. Curry, Jr.

DATE: 4/20/92

STATE CORPORATION COMMISSION  
RECEIVED  
APR 22 1992  
CONSERVATION DIVISION  
Wichita, Kansas

0

PROPOSED METHOD OF PLUGGING (CONTINUED):

hole & fill hole with mud to 33'. Pump 10 sx cement at 33' to 3' & cut off & cap 8-5/8" 3' below G.L.

BRU 22-1

SCHLUMBERGER		INDUCTION - ELECTRICAL LOG				
SCHLUMBERGER WELL SURVEYING CORPORATION HOUSTON TEXAS						
COUNTY: MORTON FIELD or BERRYMAN LOCATION SEC. 9-335-41W WELL: IVAN MILLS #1 COMPANY: THOMAS & BREWER	COMPANY	THOMAS & BREWER			Other Surveys	SL-CAL
	WELL	IVAN MILLS #1			Location of Well	SE-SW
	FIELD	BERRYMAN			Elevation: D.F.:	---
	LOCATION	SEC 9-335-41W			K.B.:	3427
	COUNTY	MORTON			or G.L.:	3416
STATE	KANSAS			FLING No.		
RUN No.	ONE					
Date	12-5-62					
First Reading	5445					
Last Reading	1493					
Feet Measured	3952					
Csg. Schlum.	1493					
Csg. Driller	1498					
Depth Reached	5446					
Bottom Driller	5450					
Depth Datum	KB					
Mud Not.	CHEMICAL					
Dens. Visc.	9.542					
Mud Resist.	2.0260					
Res. BHT	1.05 @ 115					
Rmf	.76 @ 115					
Rmc	.9					
pH	8.50					
Wtr. Loss	7.2 @ 30 min.					
Bit Size	7 7/8"					
Spags. - AM	16"					
- MN	34"					
- IND.	67760					
Cor. Rig Time	3 1/2 HOURS					
Truck No.	2531-LIBERAL					
Recorded By	WINSHALL					
Witness	REYNOLDS					

Reproduced By  
 Panhandle Electrical Log Service  
 Dallas 2, Texas

REFERENCE P67680

COMPLETION RECORD

SPUD DATE

COMP DATE

DST RECORD

RECEIVED  
 STATE CORPORATION COMMISSION  
 APR 22 1963  
 REGISTRATION DIVISION  
 Wichita, Kansas

Joan Finney  
Governor

Jim Robinson  
Chairman

F. S. Jack Alexander  
Commissioner

Rachel C. Lipman  
Commissioner

Judith McConnell  
Executive Director

Brian Moline  
General Counsel



# Kansas Corporation Commission

## NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

April 23, 1992

Merrico Resources Inc  
Box 849  
Ardmore OK 73402

Berryman Richfield  
Unit 22-1  
SE NW  
Sec. 09-33-41W  
Morton County

Dear Operator:


This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). Failure to do so is punishable by an administrative penalty of up to \$1000. If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

  
David P. Williams  
Production Supervisor

District: #1 304 W. McArtor  
Dodge City, KS 67801  
(316) 225-6760

Conservation Division  
William R. Bryson  
Director

200 Colorado Derby Bldg.  
202 W. 1st Street

Wichita, Kansas 67202-1286  
Telephone (316) 263-3238