

15-129-10588-0001

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 2/89

**WELL PLUGGING APPLICATION FORM**  
(File One Copy)

Not Assigned

API NUMBER Completed 1962 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Merrico Resources, Inc. OPERATOR'S LICENSE NO. 03408 5-92

ADDRESS P. O. Box 849, Ardmore, OK 73402 PHONE # (405) 226-6700

LEASE (FARM) Berryman-Richfield Unit                      WELL NO. 27-5 WELL LOCATION NW SW COUNTY Morton

SEC. 16 TWP. 33S RGE. 41 ( or (W)) TOTAL DEPTH 5450' PLUG BACK TD 5092'

**Check One:**

OIL WELL  GAS WELL  D & A  SWD or INJ WELL  DOCKET NO. E-18039

SURFACE CASING SIZE 8-5/8" SET AT 1507' CEMENTED WITH 625 SACKS

CASING SIZE 4-1/2" SET AT 5120' CEMENTED WITH 175 SACKS

PERFORATED AT 5030-39'; 5044-45'

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Set CIBP over existing perms w/20' cement on top. Shoot pipe at free point & pull to bottom of surface pipe & pump 50 sx cement through csg, if csg is good. If not, run 2-3/8" to cement with. Pump 35 sx cement at 700'. Pull out of (If additional space is needed use back of form.) (SEE REVERSE)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Unknown  
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Upon Commission Approval

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

David Releford PHONE # (316) 592-4321

ADDRESS P. O. Box 484, Elkhart, KS 67950

PLUGGING CONTRACTOR Sargents Casing Pullers LICENSE NO. 6547 6-92

ADDRESS P.O. Box 506, Liberal, KS 67905-0506 PHONE # (316) 624-7455

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: W. B. Curry, Jr.  
(Operator or Agent) W. B. Curry, Jr.

DATE: 4/20/92

RECEIVED  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita, Kansas

11

PROPOSED METHOD OF PLUGGING ( CONTINUED):

hole & fill hole with mud to 33'. Pump 10 sx cement at 33' to 3' & cut off & cap 8-5/8" 3' below G.L.


27-5  
BRU # 27-5

SCHLUMBERGER	
COUNTY HORTON FIELD or LOCATION WELL COMPA THOMAS & BREWER	COMPANY THOMAS & BREWER WELL GOVERNMENT #5 FIELD BERRYMAN LOCATION SEC 16-33S-41W COUNTY HORTON STATE KANSAS
	Location of Well C-NW-SW 27-5 Elevations D.F., 3441 K.B., 3443 or G.L., 3433
	FILING No.
RUN No.	ONE
Date	10-14-62
First Reading	5447
Last Reading	1510
Feet Measured	1937
Csg. Schlum.	1510
Csg. Driller	1507
Depth Reached	5443
Location Driller	5450
Depth Datum	KB 1017GL
Mud Mat.	CHEMICAL
Dens. / Visc.	9.2 / 14.8
Mud Resist.	165 @ 28"
" Res. BHT	172 @ 120"
" Rmf	115 @ 87" 85 @ 120"
" Rmc	-- @ --"
" RFI	2.5 @ --"
" Wtr. Loss	6 CC30 min. CC30 min. CC30 min. CC30 min.
Bit Size	7 7/8"
Spgrs. - AM	15"
" MN	30"
" IND.	6FF10
Opr. Log Time	1.5 HOURS
Truck No.	2509-LIBERAL
Recorded By	UNDERWOOD
Witness	TAYLOR

Reproduced By  
Panhandle Electrical Log Service  
Dallas 2, Texas

REFERENCE P6670C

14 COMPLETION RECORD

JBL	COT
KRW	PEC
JHM	JES
	EIB
	AJH
RGS	File

SPUD DATE	
COMP DATE	
DST RECORD	
CASING RECORD	
PERFORATING RECORD	
ACID, FRAC SHOT	

Joan Finney  
Governor

Jim Robinson  
Chairman

F. S. Jack Alexander  
Commissioner

Rachel C. Lipman  
Commissioner

Judith McConnell  
Executive Director

Brian Moline  
General Counsel



# Kansas Corporation Commission

## NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

April 23, 1992

Merrico Resources Inc  
Box 849  
Ardmore OK 73402

Berryman Richfield  
Unit 27-5  
NW SW  
Sec. 03-33-41W  
Morton County

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). Failure to do so is punishable by an administrative penalty of up to \$1000. If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in cursive script, appearing to read "David P. Williams".

David P. Williams  
Production Supervisor

District: #1 304 W. McArtor  
Dodge City, KS 67801  
(316) 225-6760

Conservation Division  
William R. Bryson  
Director  
200 Colorado Derby Bldg.  
202 W. 1st Street  
Wichita, Kansas 67202-1286  
Telephone (316) 263-3238