

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-189-21,397-0000 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR McCoy Petroleum Corporation OPERATOR'S LICENSE NO. 5003

ADDRESS 110 S. Main, Suite 500, Wichita, KS PHONE # (316) 265-9697

LEASE (FARM) Schmidt "A" WELL NO. 1-5 WELL LOCATION C NW NW COUNTY Stevens

SEC. 5 TWP. 33 RGE. 37 or (W) TOTAL DEPTH 6640' PLUG BACK TD _____

Check One:

OIL WELL _____ GAS WELL _____ D & A SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8-5/8" SET AT 1763' CEMENTED WITH 625 SACKS

CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

PERFORATED AT _____

CONDITION OF WELL: GOOD POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING Plug using Halliburton pump truck using 60-40 pozmix, 6% gel.

Set 1st plug @ 3000' w/100 sacks, 2nd plug @ 1800' w/50 sacks, 3rd plug @ 650' w/30 sacks

top plug @ 40' w/10 sacks. 15 sacks in rathole. 10 sacks in mouse hole.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? _____ IS ACO-1 FILED? Yes
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 12-09-89 7:00 A.M.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE
RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS: _____

Eugene Saloga PHONE # (316) 356-3510

ADDRESS Garden City, Kansas

PLUGGING CONTRACTOR Sweetman Drilling, Inc. LICENSE NO. 5658

ADDRESS 110 S. Main, Suite 500, Wichita, KS PHONE # (316) 265-5561

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: John Roger McCoy
(Operator or Agent)

DATE: 12-11-89

RECEIVED
STATE CORPORATION COMMISSION
12-12-89
DEC 12 1989
CONSERVATION DIVISION
Wichita, Kansas