

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-175-20,511-0000

LEASE NAME Johnson

WELL NUMBER #1

4290 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 16 TWP. 34S RGE. 32 (E) or (W)

COUNTY Seward

Date Well Completed 3-9-81

Plugging Commenced 4-11-85

Plugging Completed 4-16-85

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR IREX Corp.

ADDRESS 1331 17th Street, Suite 800, Denver, CO 80202

PHONE#(303) 292-9900 OPERATORS LICENSE NO. 5760

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? KCC- Wichita, KS

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation St. Genevieve Depth to Top 6355' Bottom 6366' T.D. 6400'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Morrow	Water	0'	6400'	5 1/2"	148 jts	52 jts
Chester	Oil & Water					
St. Genevieve	Oil					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Shot & Started pulling pipe @ 2310'. Pmp'd 40 sx class "H" cem frm 2306'-2206'. Pulled 18 jts csg & pmp'd 40 sx class "H" cem frm 1604'-1504'. Pulled 17 jts, pmp'd 40 sx frm 860'-760'. Pulled 17 jts, capped well w/10 sx class "H" cem from 4'-40'. Total 130 sx of cem.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Western Co. License RECEIVED

Address Woodward, OK STATE CORPORATION COMMISSION

STATE OF Colorado COUNTY OF Denver, ss. MAY 9 1985

William H. Bayliff (Employee of Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) William H. Bayliff

(Address) IREX Corp., Suite 800

SUBSCRIBED AND SWORN TO before me this 22nd day of May, 19 85

Deborah M. Olson
 1331-17th #800 Notary Public Denver, CO 80202

My Commission Expires: 8-18-85