

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-189-20746-0000

LEASE NAME COULTER #3 UNIT

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 5

1320 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 19 TWP. 33S RGE. 37W(E) or (W)

COUNTY STEVENS

LEASE OPERATOR MOBIL OIL CORPORATION

ADDRESS 2319 NORTH KANSAS, LIBERAL, KS 67901

PHONE# (316) 626-1160 OPERATORS LICENSE NO. 5208

Date Well Completed 9/26/84

Character of Well GAS

Plugging Commenced 10/9/91

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10/11/91

The plugging proposal was approved on 10/8/91 (date)

by DUANE RANKIN (KCC District Agent's Name).

Is ACO-1 filed? YES If not, Is well log attached? NA

Producing Formation LOWER MORROW Depth to Top 6030' Bottom 6128' T.D. 6290

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED
STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out
LOWER MORROW	GAS	SURFACE	1737	9 5/8"	1737	0
		SURFACE	6265	5 1/2"	6265	0

DEC 04 1991

STATE CORPORATION COMMISSION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.
SEE ATTACHED

(If additional description is necessary, use BACK of this form.)


Name of Plugging Contractor HALLIBURTON License No. _____

Address LIBERAL, KS 67901

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: MOBIL OIL CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.

R. KELLY, ENGINEERING TECHNICIAN (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) R. Kelly

(Address) 2319 NORTH KANSAS, LIBERAL, KS 67901

SUBSCRIBED AND SWORN TO before me this 3rd day of DECEMBER, 19 91

Sharon A. Cook
Notary Public

My Commission Expires: 10-1-94

PLUGGING REPORT

COULTER 3-5
 SEC 19-33-37
 STEVENS COUNTY, KS
 LOC. CODE 25566

PLUGGING PROCEDURE

9/26/91 MOVED IN PATRICK WELL SERVICE AND RIG UP. PULLED AND WAREHOUSED 3/4-7/8 RODS. RIG DOWN AND RELEASED POLE.

10/8/91 CALLED KCC DODGE CITY, SPOKE TO DAUNE RANKIN, WENT OVER PLUGGING PROCEDURE. MADE CHANGES PER KCC RECOMMENDATIONS. ADD 200' OF CMT TO CHASE PLUG AND CIRCULATE 5.5 CSN AND ANNULUS W/40-60 POZMIX, 8% GEL.

10/9/91 MOVED IN BORDER-LINE WELL SERVICE AND RIG UP. UNFLANGED TBG. HEAD AND PULLED 192 JTS OF 2 7/8 TBG., SN, TA, MA. ROSEL WIRELINE SERVICE ON LOCATION. RAN IN WITH CIBP AND SET AT 6000' KB. RAN IN WITH BAILER AND PLACED 2 SX OF CMT ON PLUG. RAN IN 4 CSN GUN AND PERFORATED 5.5 CSN AT 1787' KB., 50' BELOW SURFACE PIPE. RAN IN SOME TBG., SION.

10/10/91 RAN IN REST OF TBG., LANDED AT 5909+- . HALLIBURTON ON LOCATION. CIRCULATED 122 BLS OF 9# 36 VIS MUD. PULLED 88 JTS., AT 3203'+- . BALANCED IN 85 SX 50/50 POZMIX, FLUSHED W/MUD. POOH W/TBG. REMOVED TBG. HEAD HOOK UP TO 5.5 CSN CIRCULATED 450 SX 40/60 POZMIX W/8% GEL. CIRCULATED TO PERFS AT 1787, UP ANNULUR TO SURFACE. HAD GOOD CMT RETURN. CLEANED LOCATION, RIG DOWN BORDER-LINE AND RELEASED. ALL CIRCULATED MATERIAL WAS CIRCULATED INTO FRAC TANK AND HAULED OFF. KCC INSPECTOR ON LOCATION GLEN BARLOW. SION

10/11/91 F&O CONT. AND WILLIAMS WELDING ON LOCATION. DUG DOWN AROUND WELL HEAD, CONDUCTOR PIPE ONLY DOWN APPROX. 3', DUG ON DOWN BELOW CONDUCTOR PIPE. CUT OFF CONDUCTOR PIPE, SURFACE AND PRODUCTION STRING. WELDED ON CAP ON SURFACE PIPE AND BACK FILLED. TOTAL DEPTH 5 TO 6' DEEP. CLEANED LOCATION. PLUGGING JOB COMPLETE!

TOM ROMERO
 PRODUCTION TECH

CC. REGULATORY RAE KELLY ✓
 CC. ENGINEERING STAFF
 CC. FILE

