

10-10 128 R

To: 1 020414  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 189-20,746 -0000  
C SE, SEC. 19, T 33 S, R 37 W/2  
1320 feet from S section line  
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5208  
Operator: Mobil Oil Corporation  
Name & Address: 2319 N. Kansas  
Liberal, KS 67901

Lease Name Coulter #3 Unit Well # 5  
County Stevens 216.77  
Well Total Depth 6670 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 9 5/8 feet 1737

Abandoned Oil Well Gas Well  Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Mobil Oil Corporation License Number 5208  
Address 2319 N. Kansas, Liberal, KS 67901

Company to plug at: Hour: 8 a.m. Day: 10 Month: 10 Year: 19 91

Plugging proposal received from Tom Romero

(company name) Mobil Oil Corp. (phone) 316-544-5528

were: 5 1/2" at 6270', TOC 2450', CIBP at 6090', PRTD 6205', Perfs at 6030-36', 3207-10'  
1st plug set CIBP at 6000' with 2 sx cement on top, load hole with mud,  
2nd plug pump 85 sx cement at 3210-2400'.  
3rd plug perforate at 1787' and circulate cement to surface with tubing.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part None

Operations Completed: Hour: 5:30 p.m. Day: 10 Month: 10 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug set CIBP at 6000' with 2 sx cement on top,  
2nd plug loaded hole with mud, pumped 85 sx 50/50 Pozmix at 3210-2400',  
3rd plug perforated at 1787' and circulated cement to surface with tubing-used 60/40  
Pozmix 8% gel. 300 SX.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 22 1991

Remarks: Cemented by Halliburton. No casing recovery.  
(if additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION  
Wichita Kansas

INVOICED  
observe this plugging.

Signed Glenn R. Barlow (TECHNICIAN)

DATE 11-6-91  
INV. NO. 33629  
10-10