

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-189-20,352-0000

LEASE NAME ROBERTS "A"

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

1250 Ft. from S Section Line

2690 Ft. from E Section Line

LEASE OPERATOR Anadarko Petroleum Corporation

SEC. 20 TWP. 33S RGE. 37 (X) or (W)

ADDRESS P.O. Box 351, Liberal, Kansas 67905-0351

COUNTY Stevens

PHONE#(316) 624-6253 OPERATORS LICENSE NO. 4549

Date Well Completed 8-24-77

Character of Well Gas

Plugging Commenced 2-15-91

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 2-15-91

The plugging proposal was approved on February 10, 1991 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? -

Producing Formation Morrow Depth to Top 6082 Bottom 6115 T.D. 6600

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD RECEIVED STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	1709	0
				4 1/2	6224	2100'

MAR 15 1991

CORPORATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Set CIBP @ 6030, dmpd 2 sxs cmt on CIBP. Back off csg @ 1487. Spot 30 sxs cmt 1456-1370, 30 sxs cmt 712-626, 15 sxs cmt @ 50-3. Rec 50 jts 11.6#, 4 1/2" csg. Restored location.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address Box 506, Liberal, Kansas 67905-0506

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kansas COUNTY OF Seward, ss.

Beverly J. Williams, Engineering Technician (Employee of Operator) or (~~Operator~~) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Beverly J. Williams
Beverly J. Williams, Eng. Tech.
(Address) P.O. Box 351, Liberal, KS 67905-0351

SUBSCRIBED AND SWORN TO before me this 14 day of March, 19 91

C Cheryl Steers
Notary Public

My Commission Expires:

