


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Morton County. Sec. 18 Twp. 33S Rge. 41 (E) (W)
Location as "NE/CNW/SE" or footage from lines. 100' N. of C NW SE
Lease Owner J. M. Huber Corporation
Lease Name Borth Well No. 1
Office Address Box 978, Liberal, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 10-22 19 65
Application for plugging filed 10-25 19 65
Application for plugging approved 10-23 19 65
Plugging commenced 10-23 19 65
Plugging completed 10-23 19 65
Reason for abandonment of well or producing formation Nonproductive

NORTH



Locate well correctly on above
Section Flat

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh E. Scott
Producing formation None Depth to top _____ Bottom _____ Total Depth of Well 5080 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>Morrow</u>	<u>Salt Water</u>	<u>4985</u>	<u>5022</u>	<u>8 5/8"</u>	<u>1484'</u>	<u>●</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole was filled with mud. A 35 sack cement plug was circulated down to 700' (bottom) with top @ 600'. Hole was filled with mud to 45'. Forty-five feet to surface was filled with cement.

RECEIVED
STATE CORPORATION COMMISSION

OCT 26 1965

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lehmann-Johnson Drilling Co., Inc.
Address Evansville, Indiana

STATE OF Kansas, COUNTY OF Seward, ss.
Harold Jones (employee of owner) or owner or operator of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harold Jones
Box 978, Liberal, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 25th day of October, 19 65

My commission expires September 4, 1968

Pauline K. Wilson
Notary Public.

BORTH #1

Location: App C NW SE Commences: 10-11-65
 Sec 18 T33S R41W Completed: 10-21-65
 Morton County, Kansas

Contractor: Lohmann-Johnson Drilling Company, Inc.
 320 Indiana Bank Building
 Evansville, Indiana

Casing Record: 37 Joints 8 5/8" casing
 cemented with 550 sxs. 50-50
 Posmix w/ 2% CaCl and 100 sxs.
 60-40 Posmix w/2% CaCl.

LOG

Sand, clay	0- 580
Red bed, sand, gyp	580-1,030
Sand & Shale	1,030-1,470
Shale & Anhydrite	1,470-1,485
Red Cave Sand & Shale	1,485-2185
Shale	2,185-2,695
Shale & Lime	2,695-3,340
Lime	3,340-3,460
Lime & Shale	3,460-3,618
Lime	3,618-3,909
Lime & Shale	3,909-4,040
Lime	4,040-4,255
Lime & Shale	4,255-4,385
Lime	4,385-4,987
Shale, Lime, Shale	4,987-5,080

RECEIVED
 STATE CORPORATION COMMISSION

NOV 24 1965

CONSERVATION DIVISION
 Wichita, Kansas

I, Harold Jones, employed by J. M. Huber Corporation, certifies that the above log is a true and correct copy of the formations encountered in drilling the above mentioned well, as taken from the Daily Drilling Report.

J. M. Huber Corporation
 Box 978
 Liberal, Kansas

by

Harold Jones
 Harold Jones

BORTH #1

Location: App C NW SE Commence: 10-11-65
Sec 18 T33S R41W Completed: 10-21-65
Morton County, Kansas

Contractor: Lohmann-Johnson Drilling Company, Inc.
320 Indiana Bank Building
Evansville, Indiana

Casing Record: 37 Joints 8 5/8" casing
cemented with 550 sxs. 50-50
Posmix w/ 2% CaCl and 100 sxs.
60-40 Posmix w/2% CaCl.

LOG

Sand, clay	0- 580
Red bed, sand, typ	580-1,030
Sand & Shale	1,030-1,470
Shale & Anhydrite	1,470-1,485
Red Cave Sand & Shale	1,485-2185
Shale	2,185-2,695
Shale & Lime	2,695-3,340
Lime	3,340-3,460
Lime & Shale	3,460-3,618
Lime	3,618-3,909
Lime & Shale	3,909-4,040
Lime	4,040-4,255
Lime & Shale	4,255-4,385
Lime	4,385-4,987
Shale, Lime, Shale	4,987-5,080

RECEIVED
NOV 24 1965
MORTON COUNTY DIVISION
MORTON COUNTY, KANSAS

I, Harold Jones, employed by J. M. Huber Corporation, certifies that the above log is a true and correct copy of the formations encountered in drilling the above mentioned well, as taken from the Daily Drilling Report.

J. M. Huber Corporation
Box 978
Liberal, Kansas
by Harold Jones
Harold Jones