

15-129-20006-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Morton

County. Sec. 20 Twp. 33S Rge. 41 (E) W (W)

Location as "NE/CNW/SW" or footage from lines 1980' from east; 660' from north

Lease Owner Mesa Petroleum Co.

Lease Name Government Well No. 2-20

Office Address P. O. Box 2009, Amarillo, Texas

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed May 24, 19 67

Application for plugging filed May 25, 19 67

Application for plugging approved _____ 19 _____

Plugging commenced May 24, 19 67

Plugging completed May 24, 19 67

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production NA 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Edgar J. Eves, Sublette, Kansas

Producing formation None Depth to top _____ Bottom _____ Total Depth of Well 5100 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
None				8 5/8"	1484	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Spotted 35 sacks cement - plug at 700 feet, loaded with heavy mud back to 40 feet, spotted 15 sacks cement - plug from 40 feet to bottom of cellar, cut off 3 feet below GL.

RECEIVED
STATE CORPORATION COMMISSION

MAY 28 1967

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Garvey Drilling Co. & HOWCO
Address 512 Cravens Building, Oklahoma City, Oklahoma

STATE OF TEXAS, COUNTY OF POTTER, ss.
J. L. Farrell (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *J. L. Farrell*
Box 2009 Amarillo Texas 79105
(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of May, 19 67

My commission expires June 1, 1969 *2 L Shife* Notary Public.



15-129-20006-0000

RECEIVED
STATE CORPORATION COMMISSION

MAY 29 1967

CONSERVATION DIVISION
Wichita, Kansas

MESA NO. 2-20 Government
Section 20, T33S-R41W
Morton County, Kansas

<u>FORMATION</u>	<u>TOP</u>	<u>BOTTOM</u>
Surface sand	0	100
Caliche	100	600
Red Shale	600	1920
Anhydrite	1920	2610
Dolomite	2610	2790
Broken Lime & Shale	2790	3800
Shale	3800	3940
Lime	3940	4170
Shale	4170	4220
Lime	4220	4250
Shale	4250	4468
Lime	4468	4712
Shale	4712	4784
Broken Lime & Shale	4784	4912
Shale (Morrow)	4912	4960
Sand	4960	4972
Shale	4972	5030
Sand	5030	5090
Shale	5090	5100