


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Morton County. Sec. 20 Twp. 33 Rge. 41 (E) (W)
Location as "NE/CNW/SW" or footage from lines C SW
Lease Owner Panhandle Eastern Pipe Line Company
Lease Name U. S. Government "A" Well No. 1
Office Address Box 979, Liberal, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 11 1961
Application for plugging filed July 28 1961
Application for plugging approved Yes 1961
Plugging commenced August 11 1961
Plugging completed August 11 1961
Reason for abandonment of well or producing formation Dry Hole



If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3514 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>Wabaunsee</u>		<u>2972</u>	<u>80</u>		<u>8 5/8 603'</u>	<u>None</u>
<u>Wabaunsee</u>		<u>2929</u>	<u>50</u>		<u>4 1/2" 3303'</u>	<u>1411'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 2500', bottom was already plugged off, pulled pipe, mudded hole to 400', set 10' rock bridge, dumped 20 sacks of cement, cement filled to 3307', filled hole to 40', set 10' rock bridge, ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
SEP 24 1961
9-14-61
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Knight Casing Pulling Company
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Seward, ss.
R. L. O'Shields (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. L. O'Shields
P. O. Box 979, Liberal, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of September, 1961

MY COMMISSION EXPIRES SEPT. 29, 1964 Ronald L. Vanjesson Notary Public.
My commission expires _____



RP

DRILLER'S LOG

WELL NAME: U. S. Government A No. 1; COMPANY OPERATING: Panhandle Eastern Pipe Line Co
 ADDRESS of COMPANY: Box 371, Liberal, Kansas
 979
 WELL LOCATION: 1/4 C 1/4 SW 1/4,
ft. North of South line,
ft. East of West line; Sec. 20, Twp. 33, Rge. 41, Morton County, Kansas
 DRILLING STARTED June 19, 1961; DRILLING COMPLETED June 29, 1961
 WELL COMPLETED August 11, 1961; WELL CONNECTED _____, 19____
 ELEVATION: 3436 ft. Ground Level; CHARACTER OF WELL (Oil, Gas, or Dry Hole) Dry Hole

OIL OR GAS SANDS OR ZONES - PERFORATIONS - ACIDIZING AND FRACTURING INFORMATION					
Name	From	To	No. of Shots	Gallons Used	Kind Used
Wabaunsee	2972	80	32	500	Mud Acid
Wabaunsee	2929	50	36	1000	15%

CASING RECORD

Size	Amount Set	Sacks of Cement	Amount Pulled
8 5/8"	603'	375	None
4 1/2"	3308'	250	1411'

FORMATION RECORD

Formation	Top	Bottom	Formation	Top	Bottom
Sand	0	587			
Red Bed	587	963			
Red Bed, Sand & Gyp.	963	1507			
Anhydrite & Red Bed	1507	1731			
Anhydrite, Gyp. & Shells	1731	1956			
Shale, Sand & Anhydrite	1956	2107			
Anhydrite	2107	2110			
Anhydrite & Shale	2110	2293			
Lime & Shale	2293	2590			
Lime	2590	2595			
Lime & Shale	2595	3510			
Total Depth	3510				

RECEIVED
 BY STATE COMMISSIONER
 SEP 14 1961
 CONSERVATION DIVISION
 WICHITA, KANSAS

RESULTS of INITIAL PRODUCTION TEST: _____