

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 • Finney State Office Building  
 130 South Market, Rm 2078  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-129-21408 - 0000

LEASE NAME USA BERRYMAN "B"

WELL NUMBER 3H

3730 Ft. from S Section Line

1450 Ft. from E Section Line

SEC. 21 TWP. 33 RGE 41 (E) or (W)

COUNTY MORTON

Date Well Completed 11-29-95

Plugging Commenced 4-22-97

Plugging Completed 4-27-97

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # ( 316 ) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-22-97 (date)

by MR. STEVE MIDDLETON (KCC District Agent's Name)

Is AC0-1 filed? YES If not, is well log attached? \_\_\_\_\_

Producing Formation NONE Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 6550

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size  | Put In | Pulled Out |
|-----------|---------|------|----|-------|--------|------------|
|           |         |      |    | 8 5/8 | 753    | NONE       |
|           |         |      |    | 5 1/2 | 2402   | 380'       |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set. TIH W/1 1/2" TBG TO 2202' & PMPD 35 SXS CLASS "H" & 15 SXS HULLS FROM 1842 TO 2202. CIRC. HOLE W/9 PPG MUD. TAG TOP OF CMT PLUG AT 1902. PULLED TBG TO 803. PMPD 30 SXS CLASS "H" CMT FROM 803 TO 538. TOH W/TBG. SHOT OFF 5 1/2" CSG @ 380'. CIRC HOLE W/9 PPG MUD. PMPD 35 SXS CMT FROM 265-380. PULLED CSG TO 80'. PMPD 25 SXS CMT FROM 80-0. TOH W/5 1/2" CSG (TOT 92 FT). CUT OFF & CAP 8 5/8 CSG 3' BELOW GL. PERMANENTLY INSCRIBE WELL NAME, NUMBER AND DATE PLUGGED ON CAP. KCC WITNESS STEVE MIDDLETON.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT & HORTON PLUGGING, INC. License No. 31151

Address RT 1, BOX 49A, TYRONE, OKLAHOMA 73951-9731 PHONE: (405) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.

L. MARC HARVEY (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) L. Marc Harvey  
 L. MARC HARVEY, DRILLING TECHNICAL ASSISTANT

(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 5th day of May, 1997

My Commission Expires: 5-15-99  
 FRED A. WINZ  
 Notary Public - State of Kansas  
 My Appt. Expires

RECEIVED  
 CORP COMM  
 5-7-97  
 7 A.M. 11:46