

STENCILED

NOV 10 1945

RICHMOND & REIGLE
Forney Well No. 3

15-191-01345-0000
ORIGINAL

S. 13 T. 30 R. 1 W
C NW NW
Sumner County, Kansas
Production
Elevation 1234

Total Depth (rotary) 3845
Total Depth (cable) 3869
Drilling began 7-27-45 (rotary)
Drilling comp. 8-27-45 (")
Drilling began 9-3-45 (cable)
Drilling comp. 9-6-45 (")

Casing
10" 196'
8 5/8 300'
5 1/2 3845'

*swab 43 Bbls oil
8 hr*

Figures Indicate Bottom of Formations

Sand & shale	197	
shale & shells	480	
lime	520	
shale & shells	685	
lime & shale	2115	
lime	2160	
broken lime	2275	
lime & shale	2820	Top Kansas City 2820
lime	3132	
lime & shale	3419	Top Miss. lime 3419
lime	3776	Base Miss. lime 3776
lime & shale	3845	Top black shale 3777

Total Depth with Rotary Tools 3845

Cable Tool Drilling.

Shale	3851	
Sand	3853 1/2	Some free oil
Sand, Hard	3861	
Shale and Sand	3869	

Total Depth 3869 Sept. 8. Swabbed 43 Bbls. Oil in 8 hours.

RECEIVED
STATE CORPORATION COMMISSION

APR 30 1979

CONSERVATION DIVISION
Wichita, Kansas