


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

9

NORTH



Locate well correctly on above
Section Plat

Sumner County. Sec. 12 Twp. 30 Rge. 1W (E1) (W)
Location as "NE/CNW/SW" or footage from lines. 0 NE SW
Lease Owner Plains Exploration Company
Lease Name Long Long Well No. 5
Office Address 1135 Petroleum Club Bldg - Denver 2, Colo.
Character of Well (completed as Oil, Gas or Dry Hole) D&A
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced _____ March 25 19 64
Plugging completed _____ April 5 19 64
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes
Name of Conservation Agent who supervised plugging of this well Howard Hess

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3877' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled back in the 5" with crushed gravel. Dumped 4 sacks of cement.
Shot pipe off at 2461'. Pulled pipe and mudded hole to 250'. Set rock bridge and dumped 20 sacks of cement. Mudded to 20'; set rock bridge and dumped 5 sacks of cement at base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

APR 23 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Bert Self
Address Hutchinson, Kans.

STATE OF Kansas, COUNTY OF Reno, ss.
Employee _____ (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bert Self
R. R. #4, Hutchinson, Kans.
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of April, 19 64

Notary Public.

My commission expires October 18, 1965



WELL LOG

9

COMPANY **Plains Exploration Co.**

SEC. **12** T. **30S** R. **1W**

FARM **Long** NO. **5**

LOC. **NE SW**

TOTAL DEPTH **3850'**

COUNTY **Sumner**

COMM. **2-19-64**

COMP. **3-2-64**

CONTRACTOR **Garvey Drilling Company**

CASING **8 5/8" @ 271' w/200 sx**

5 1/2" @ 3844' w/75 sx

ELEVATION **1234' DF**
1236' KB

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

110 Sand and Shale
 273 Shale and Lime
 815 Lime
 1680 Lime and Shale
 2660 Shale and Lime
 3296 Lime
 3400 Lime and Shale
 3753 Lime
 3843 Shale and Lime
 3850 Simpson
 3850 RTD

TOP OF FORMATION BY GEOLOGIST
All Measurements from Kelly Bushing.

KANSAS CITY- 2808' (-1572')

Mississippian- 3419' (-2193')

Kinderhook- 3752' (-2516')

Simpson- 3842' (-2607')

CABLE TOOL REPORT ADDED MARCH 20, 1964

Drilled to 3877' with Cable Tools.

Four hour swab test showed well to be making approximately 4 barrel per hour total fluid; about 1 1/2 per cent oil.

Shut down for abandonment, March 13, 1964.

E. E. Duncan

RECEIVED
STATE CORPORATION COMMISSION

MAR 26 1964

CONSERVATION DIVISION
Wichita, Kansas

State of Kansas }
County of Barton } ss

I, Sam N. Stephens of Garvey Drilling Company

upon oath state the above and foregoing is a true and correct copy of the log of the Long #5 well.

Sam N. Stephens

Subscribed and sworn to before me this 10th day of March 1964

My Commission Expires: September 23rd, 1967

Edward C. Jasin
NOTARY PUBLIC