


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Sumner County, Sec. 12 Twp. 30 Rge. 14 E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
C S/2 SE SW
Lease Owner Raymond Oil Co., Inc.
Lease Name Long #1 Well No.
Office Address Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plot

Date Well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 3/10/78 19
Plugging completed 3/17/78 19
Reason for abandonment of well or producing formation
depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Barnett
Producing formation Depth to top Bottom Total Depth of Well 3849
Show depth and thickness of all water, oil and gas formations.

| OIL, GAS OR WATER RECORDS | | | | CASING RECORD | | | |
|---------------------------|-------------|---------|------|---------------|--------|--------|------------|
| DATE | DESCRIPTION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
| MAR 25 1978 | | | | | 8-5/8 | 270 | none |
| | | | | | 5 1/2" | 3839 | 3053' |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

Sanded to 3800' and set 5 sacks cement. Loaded casing with water, shot pipe at 3215',
3122', 3028', pulled 100 joints of 5 1/2" casing. Bailed hole to 280', set rock bridge and
ran 4 yards ready mix.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor VOTH CASING PULLING
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
WALTER VOTH (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Walter Voth
CHASE, KANSAS (Address)

SUBSCRIBED AND SWORN TO before me this 21st day of March, 19 78

My commission expires MARGARET MELCHER
Rice County, Ks.
My Comm Exp. Feb. 15, 1979

Margaret Melcher
Notary Public.

15-191-01341-0000
 COPY


WELL LOG BUREAU-- KANSAS GEOLOGICAL SOCIETY
 412 Union National Bk. Bldg., Wichita, Kansas

Company - PLAINS EXPLORATION CO.
 Farm - Long No. 1

SEC. 12 T. 30S R. 1W
 C S/2 SE/4 SW/4

Total Depth. 3849'
 Comm. 6-5-47 Comp. 7-4-47
 Shot or Treated. None
 Contractor. Sterling Drilling Co.
 Issued. 9-27-47

County. Sumner
 KANSAS



Elevation. 1235

Production. Approx. 43 bbls. per day.

CASING:

272' of 8 5/8" cas w/150 sx.
 6 1/2" casing set at 3854' cas. w/100 sx.
 All measurements carried from Kelly bushing
 Figures indicate Bottom of Formations.

| | |
|---------------------|------|
| Kelly Bushing | 0 |
| sand | 50 |
| shale | 200 |
| lime | 325 |
| shale & lime shells | 540 |
| lime | 815 |
| shale | 915 |
| shale & shells | 1146 |
| sand | 1205 |
| shale | 1250 |
| shale & shells | 1800 |
| lime | 1890 |
| shale & lime | 2360 |
| shale & shells | 2450 |
| shale | 2590 |
| shale & lime | 2700 |
| shale | 2836 |
| lime | 3030 |
| lime & shale | 3080 |
| lime | 3115 |
| lime broken | 3205 |
| lime & shale | 3270 |
| shale | 3417 |
| lime | 2800 |
| shale | 3839 |
| sand | 3840 |

Rotary Total Depth

| | |
|-------------|------|
| sand | 3849 |
| Total Depth | 3849 |

TOPS:

Simpson sand, 3839'--no show after drilling plug and cleaning out to bottom. Drilled 4' of new hole--hard white sand--slight show of oil--drilled 2 more feet of hole--sand, softer. Fill up of about 1000' in 2 hrs.--some gas. Fill up of 1950' after setting 12 hrs. Drilled 3 feet of new hole--no noticeable increase. Swabbed about 3bbl. per hr. Well pumping about 43 bbls. per day after being pumped approx. 2 weeks.

RECEIVED
 STATE CORPORATION COMMISSION

DEC 15 1977

CONSERVATION DIVISION
 Wichita, Kansas