

WELL PLUGGING RECORD

FORMATION PLUGGING RECORD

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

OR

Strike out upper line
when reporting plug-
ging of formations.

Sumner County. Sec. 12 Twp. 30 Rge. 1 (E) 1 (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE SE NW

Lease Owner Sterling Drilling Company, et al

Lease Name Stunkel Well No. 1

Office Address Sterling, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed November 14, 19 48

Application for plugging filed November 15, 19 48

Application for plugging approved November 15, 19 48

Plugging commenced November 15, 19 48

Plugging completed November 21, 19 48

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well W. G. Buffington

Producing formation Depth to top Bottom Total Depth of Well 3890 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	219	
				4-1/2"	3892.62	3357.15

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with rock up to 3835. Dumped 5 sacks cement. Filled with mud to bottom of surface pipe (210'). Set bridge. Dumped 10 sacks cement. Filled with mud to top with 10 sacks cement at surface.

RECEIVED

Conservation Div.

DEC 11 1948

STATE CORPORATION
COMMISSION
KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Sterling Drilling Company
Address Sterling, Kansas

STATE OF Kansas, COUNTY OF Rice, ss.

Rollin Mead (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Rollin Mead

Sterling, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 29th day of November, 19 48.

My Commission Expires August 17, 1949

My commission expires

22-2025 2-48-15M

PLUGGING
FILE SEC 12 T 30 R 16
BOOK PAGE 68 LINE 35

Notary Public.

Location - SE SE NW of Section 12-30S-1W, Sumner County, Kansas.

Owner - Sterling Drilling Company, et al
Contractor - Sterling Drilling Company

Commenced - 7-29-48
Completed - 8-17-48 (w/r)
11-21-48 (plugged & abandoned)

Total Depth - 3846' (w/r)
3890' (c/t)

ELEVATION - 1239 D.F.
1236 Gr.

LOG

0- 40	Surface
40- 185	Shale and Shells
185- 200	Shale
200- 215	Lime
215- 360	Shale and Lime
360- 390	Shells
390- 540	Shale and Shells
540-1310	Shale and Lime
1310-1320	Shale
1320-1650	Shale and Shells
1650-2075	Shale and Lime
2075-2175	Lime
2175-2650	Shale and Lime
2650-2685	Lime
2685-2765	Lime and Shale
2765-2815	Shale
2815-2965	Lime
2965-2990	Lime and Shale
2990-3095	Lime
3095-3145	Lime and Shale
3145-3185	Lime
3185-3395	Lime and Shale
3395-3409	Shale
3409-3417	Chert
3417-3450	Lime
3450-3480	Lime and Shale
3480-3544	Lime
3544-3565	Shale and Lime
3565-3605	Lime
3605-3810	Lime and Shale
3810-3846	Shale
3846-3890	Cable Tools

CASING RECORD

219 Feet 8-5/8" Surface Pipe
Cemented with 150 Sacks Cement

3892.62' 4 1/2" O.D. Casing
(Set 1 1/2' off Bottom)
Cemented with 75 Sacks Cement.

FORMATION TOPS

Top Kansas City	2819	
Mississippi	3409	-2168'
Simpson	3844 1/2	-2603 1/2'
Total Depth	3846	-2605'

PRODUCTION

None. Dry and Abandoned.

Acidized with 500 Gallons.

RECEIVED

Conservation Dept.

DEC 11 1948

STATE CORPORATION
COMMISSION

I hereby certify that the above is a true and correct copy of Driller's Log of well drilled in the SE 1/4 SE 1/4 NW 1/4 OF Section 12, Township 30 South, Range 1 West, Sumner County, Kansas.

STERLING DRILLING COMPANY

By Rollin Mead
Vice-President

Subscribed and sworn to before me this 4th day of December, 1948.

PLUGGING

FILE SEC 15-30-126
My Commission Expires: August 17, 1949

Frank S. ...
Notary Public