

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Barber SEC. 18 TWP. 34S RGE. 13 E/W
 Location as in quarters or footage from lines:
C W/2 SW/4 NE/4

Lease Owner (Albert Bouziden) D & B Energy Corp.
 Lease Name Clark Well No. 18-7
 Office Address 5600 N. May Ave., Suite 145, OKC, OK. 73112
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
 Date Well Completed 10-17-82
 Application for plugging filed 11-23-82
 Plugging commenced 10-17-82
 Plugging completed 10-17-82
 Reason for abandonment of well or producing formation _____

Locate Well
 correctly on above
 Section Platt.

Dry hole
 Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Paul Luthi
 Producing formation None Depth to top N/A bottom N/A T.D. 5030'
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
		0	1103'	8 5/8	10/6/82	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.
1st cement plug at 863' to 1120' w/70 sacks, 2nd cement plug at 350' to 510' w/40 sacks, Top plug at 40' w/10 sacks above 1 sack hulls and a wood plug. All plugs displaced to balance inside and out of drill pipe w/fresh water. Cement type was 50/50 poz., 4% gel, 3% CaCl. Additional 10 sack plug placed in rathole. Remainder of hole full of approx. 9.5 lb/gal drilling mud.

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Sun Oil Well Cementing Medicine Lodge, KS

STATE OF Oklahoma COUNTY OF Oklahoma, ss.
Mark Liddell ((employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Mark Liddell
5600 N. May Ste 145 OKC, OK 73112
 (Address)

SUBSCRIBED AND SWORN TO before me this 14th day of December, 19 82

Susan A. Siffith
 Notary Public.

My Commission expires: May 12, 1984