

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-007-21,099-0000

LEASE NAME Bouziden

WELL NUMBER 18-1

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

         Ft. from S Section L

         Ft. from E Section L

SEC. 18 TWP. 34 RGE. 13 KK) or (W)

COUNTY Barber

LEASE OPERATOR Great Bend Casing Pullers, Inc.

ADDRESS P.O. Box 251, Great Bend, Kansas 67530

PHONE# (316) 793-9711 OPERATORS LICENSE NO. 4635

Date Well Completed 3-7-81

Character of Well Gas

Plugging Commenced 10-21-92

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 1:00 PM

The plugging proposal was approved on 10-21-92 (date)

by Steve Pfiefer (KCC District Agent's Name)

Is ACQ-1 filed? Yes If not, is well log attached?         

Producing Formation Morrow & Miss Depth to Top 4640 Bottom 4910 T.D. 4990

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size   | Put In | Pulled out |
|-----------|---------|------|----|--------|--------|------------|
|           |         |      |    | 10 3/4 | 246    | 0          |
|           |         |      |    | 4 1/2  | 4984   | 3217       |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other were used, state the character of same and depth placed, from          feet to          feet each  
Bottom plug: Sanded to 4550 & bailed 4 sx cement.

Top plug: Pumped 300 lb hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lb hulls, 150 sx cement (60/40 with 6% gel). Had maximum pressure of 400 lbs & shut in pressure of 200 lbs.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Great Bend Casing Pullers, Inc. License No. 4635 CP

Address Box 251, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Great Bend Casing Pullers, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Gary G. Burke

(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Gary G. Burke

(Address) Box 251, Great Bend, Kansas 67530

SUBSCRIBED AND SWORN TO before me this 22 day of October 19 92



Anna K. Burke  
Notary Public  
Conservation Division  
Wichita, Kansas

Commission Expires: 4-30-96