

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80  
**RECEIVED**  
STATE CORPORATION COMMISSION  
**DEC 29 1981**

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

CONSERVATION DIVISION  
Wichita, Kansas

COUNTY Barber SEC. 18 TWP. 34S RGE. 13 N/W  
Location as in quarters or footage from lines:  
645' S of N Line, 403' W of E Line SE/4

	18		4

Lease Owner Professional Petroleum, Inc.  
Lease Name Albert Bouziden Well No. 18-3  
Office Address 2601 NW Expressway, St 512 W-OKC, OK 73112  
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole  
Date Well Completed 12-18-81  
Application for plugging filed 12-18-1981  
Plugging commenced 12-18-1981  
Plugging completed 12-18-81  
Reason for abandonment of well or producing formation Dry Hole

Locate Well  
correctly on above  
Section Platt.

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Morris Leslie  
Producing formation Mississippi Depth to top 4724' bottom 4930' T.D. 4954'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
No Test						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set. Circulate hole with 9.2 per gallon mud, pull drill pipe to 1375', pump 60 sacks Class H cement with 2% gel, 3% calcium Chloride (cement plug 1375' to 1136'). Pull drill pipe to 375' pump one-hundred sacks Class H cement, 2% Gel, 3% calcium chloride. Cement plug 375' to 151'. Pull drill pipe to 40', pump 20 sacks of cement 2% gel, 3% calcium chloride. Circulate cement to surface. Cut surface pipe 3 feet below ground level and weld plate over the top. Circulate thru joint of drill pipe ten sacks of cement in rat hole 2% gel 3% calcium chloride. Circulate thru joint of drill pipe 5 sacks of cement in mouse hole 2% gel, 3% calcium chloride.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor B.J. Hughes

STATE OF Oklahoma COUNTY OF Oklahoma, ss.  
I. G. Purser (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) I. G. Purser  
2601 NW EXPRESSWAY, Suite 512W  
OKLA CITY, (Address) OKLA, 73112

SUBSCRIBED AND SWORN TO before me this 28th day of December, 1981

My Commission expires: My Commission Expires Oct. 19, 1985

[Signature]  
Notary Public.