


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

SUMNER County, Sec. 12 Twp. 34 Rge. (E) 3 (W)  
Location as "NE/CNW/SW" or footage from lines SW SW NE  
Lease Owner TIME PETROLEUM COMPANY  
Lease Name CINK Well No. 1  
Office Address 500 ORPHEUM BUILDING WICHITA, KANSAS  
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE  
Date well completed 8-7-54 19.  
Application for plugging filed (PHONE) 8-7-54 19.  
Application for plugging approved (PHONE) 8-7-54 19.  
Plugging commenced 8-7-54 19.  
Plugging completed 8-7-54 19.  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19.  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well W. G. BUFFINGTON  
Producing formation Depth to top Bottom Total Depth of Well 4650 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	244'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

HOLE FILLED WITH HEAVY MUD TO 244 FT. SET FIRST PLUG AT 244 FT. WITH 20 SACKS CEMENT.  
FILLED HOLE WITH HEAVY MUD TO 30 FT. SET SECOND PLUG AT 30 FT. WITH 10 SACKS CEMENT.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor BADGER DRILLERS, INC.  
Address TULSA, OKLAHOMA

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
R. R. GREENBAUM (Employer or owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *R. R. Greenbaum*  
500 ORPHEUM BUILDING WICHITA KANSAS (Address)

SUBSCRIBED AND SWORN to before me this 22 day of SEPTEMBER, 19 54

My commission expires 12-31-56 *Juan B. Fenton* Notary Public.



15-191-00609-0000

TIME PETROLEUM COMPANY

CINK NO. 1

SW SW NE Sec. 12-34S-3W  
Sumner County, Kansas

Drilling started 7-14-54  
Drilling completed 8- 7-54  
8 5/8" O.D. Casing Cemented @ 244'

<u>From</u>	<u>To</u>	<u>Formation</u>	<u>Remarks</u>
0	40	Shale - Rock	
40	281	Shale & Red Bed	248' 8 5/8" O.D. Casing Cemented at 244' with 175 sacks
281	500	Shale	
500	2860	Lime & Shale	
2860	2963	Lime	
2963	3047	Lime, Shale & Sand	
3047	3155	Lime & Shale	
3155	3241	Sandy Lime	
3241	3565	Lime & Shale	
3565	4009	Lime	
4009	4097	Lime & Shale	
4097	4547	Lime	Top of Mississippi Lime - 4191'
4547	4612	Lime & Shale	
4612	4628	Lime	
4628	4650	Sand	Total Depth - 4650'

This is a certified true copy of the Driller's Log as shown on the Daily Drilling Reports.

M. R. Maden  
BADGER DRILLERS, INC.

Subscribed and sworn to before me  
this 12th day of Aug., 1954

Opal Grubel  
Notary Public

My commission expires 10-20-57

REIVED  
COMMISSION  
AUG 23 1954  
DIVISION

PLUGGING  
FILE SEC 12-34-R-30  
BOOK PAGE 34 LINE 45