

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Sumner County, Sec. 22 Twp. 34S Rge. (E) 3 (W)

Location as "NE/CNW/SW" or footage from lines. NW NE SW

Lease Owner Herndon Drilling Co.

Lease Name A. Subera Well No. 7

Office Address Box 489 Tulsa, Okla.

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 1-22 19 58

Application for plugging filed 19

Application for plugging approved 19


Plugging commenced 7-8 19 63

Plugging completed 7-9 19 63

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 1-31 19 63

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Howard Hess

Producing formation Simpson sand Depth to top 4733' Bottom 4742' Total Depth of Well 4742' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set. Fill open hole w/gravel from 4742' to 4730'. Dump 5 sacks cement w/dump bailer. Pull 2 jts. 5 1/2" casing. Set 6' rock bridge & plug w/ 5 sacks cement. Fill up to 17' of top. Set 5' rock bridge & dump 5 sacks cement on top.

RECEIVED
STATE CORPORATION COMMISSION
AUG 15 1963
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Winfield Oil Field Ser, Inc.
Address Box 952 Winfield, Kansas

STATE OF Oklahoma, COUNTY OF Tulsa, ss.
Seth Herndon, Jr. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Seth Herndon, Jr.
Seth Herndon, Jr.
Box 489, Tulsa, Oklahoma
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of August, 1963

My commission expires June 19, 1965
Johnnie Alene Frese Notary Public.

15-191-01024-0000

R

WELL LOG ON A. SUBERA #7

Spudding date: 12/21/57
Date casing set: 12/23/57
Date rotary completed: 1/15/58
Date cable completed:

Location:

NW NE SW, Section 22-34S-3W, Sumner County, Kansas

<u>FROM</u>	<u>TO</u>	<u>FORMATION</u>	<u>REMARKS</u>
0	653	Surface hole	Ran 21 Jts. 8-5/8" 24 1/2 Casing, set at 652' and cemented w/425 sx. cement w/2% C.C.
653	3165	Lime & Shale	
3165	3225	Sand, Lime & Shale	
3225	3255	Sand & Shale	
3255	3320	Sand, Shale & Lime	
3320	3530	Lime & Shale	
3530	3617	Sand & Shale	
3617	3700	Shale & Lime	
3700	3786	Sandy Lime	
3786	3840	Lime & Shale	
3840	3920	Lime	
3920	4250	Lime & Shale	
4250	4298	Lime, Shale & Chert	
4298	4317	Chert	
4317	4352	Chert, Lime & Shale	
4352	4589	Lime	
4589	4615	Lime & Shale	
4615	4712	Lime	
4712	4742	Sand, Lime & Shale	
4742		Total Depth	Ran 155 Jts. 5 1/2" 14 1/2 Casing, set at 4733' and cemented w/250 sx. cement. DV Tool set @ 1600' w/275 sx. cement and 3% gel.

RECEIVED
STATE CORPORATION COMMISSION

AUG 15 1963

CONSERVATION DIVISION
Wichita, Kansas

Subscribed and sworn to before me this 21st
day of January, 1958

I certify the above and foregoing to be a true and exact
copy of the original driller's log on the A. Subera #7.

[Signature]
Notary Public
My commission expires: 1-27-60

HERNDON DRILLING COMPANY
By: [Signature]
Title: Assistant Secretary