


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Sumner County, Sec. 22 Twp. 34S Rge. 3W (X) (W)
Location as "NE/CNW/SW" or footage from lines 105' Southeast of NW NW SW
Lease Owner Herndon Drilling Company
Lease Name A. Subera Well No. 6
Office Address Drawer 489, Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 12/16/57 19
Application for plugging filed 12/16/57 19
Application for plugging approved 12/16/57 19
Plugging commenced 12/16/57 19
Plugging completed 12/16/57 19
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Flat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eugene Graham, Winfield, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4747 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	665'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with mud to 200 ft. Placed plug at 200 ft. and placed cotton seed hull bridge on top of plug. Put 20 gals. gravel on top of bridge and filled hole with cement to 5 ft. below ground level. Cement run by Halliburton Oil Well Cementing Company. Used 60 sx. cement.

RECEIVED
STATE CORPORATION COMMISSION

DEC 21 1957

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Herndon Drilling Company
Address Drawer 489, Tulsa, Oklahoma

STATE OF OKLAHOMA, COUNTY OF TULSA, ss.
W. G. Prather (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. G. Prather
Drawer 489, Tulsa, Oklahoma
(Address)

SUBSCRIBED AND SWORN to before me this 19th day of December, 1957

My commission expires 1/27/60

Quay Lifer
Notary Public.

PLUGGING
FILE SEC 22T 34R 3W
BOOK PAGE 70 LINE 12

15-191-01026-0000

WELL LOG ON A. SUBERA #6

Spudding date: 11/27/57
Date casing set: 11/29/57
Date rotary completed: 12/16/57
Date cable completed:

Location:

105' Southeast of NW NW SW, Section 22-34S-3W,
Sumner County, Kansas

FROM	TO	FORMATION	REMARKS
0	665	Surface Hole	Ran 21 Jts. 8-5/8" 24# Casing, set at 665' and cemented w/400 Sx. Cement w/2% C.C.
665	3302	Lime & Shale	
3302	3385	Lime	
3385	3664	Lime & Shale	
3664	3762	Lime	
3762	4281	Lime & Shale	
4281	4303	Chat	
4303	4338	Lime & Chert	
4338	4665	Lime	
4665	4735	Lime & Shale	
4735	4747	Sand	Plugged hole. Filled hole with mud to 200'. Bridged hole @ 200' and filled with 60 sx. cement to 5' below ground level.
4747		Total Depth	

RECEIVED
STATE CORPORATION COMMISSION
DEC 21 1957
CONSERVATION DIVISION
Wichita, Kansas

Subscribed and sworn to before me this 19th
day of December 19 57.

I certify the above and foregoing to be a true and exact
copy of the original driller's log on the A. Subera #6.

HERNDON DRILLING COMPANY

[Signature]
Notary Public
My commission expires: 1-27-60

By: [Signature]
Title: Assistant Secretary

PLUGGING
FILE SEC 22 T 34 R 3W
BOOK PAGE 70 LINE 12