

15-173-10045-0000

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUL 30 1973

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Sargent of J.M. Huber has this date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: J.M. Huber Corporation

Complete Address: Box 831, Borger, Texas

Lease Name: Rinehart Well No. 1

Location: C SW NE Sec. 15 Twp. 33 Rge. 31 XX (W) EE

County: Seward Total Depth 6010' Oil Well

Gas Well Input Well X SWD Well D & A Lost Hole

Mr. Sargent was instructed to plug the well as follows:

8 5/8" to 2550' circulated w/ cement. 5 1/2" to 5730' cemented.

Top perforations 5060' Plug bottom w/ 25 sacks cement.

Top of cement 4950' Mud 4950' to 900'

Spotted 35 sacks cement 900' to 800' Mud 800' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,


Conservation Division Agent