

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION
FEB 26 1974
CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Meyer of Abercrombie has this

date requested permission to plug the following described well:

Mr. Meyer guarantees payment of the plugging fee.Operator's full Name: A.L. Abercrombie Inc.Complete Address: 801 Union Center Bldg., Wichita, KansasLease Name: Wheatley "A" Well No. 1Location: SE SE Sec. 23 Twp. 33 Rge. 31 XX (E) (W)County: Seward Total Depth 5890' Oil WellGas Well Input Well SWD Well D & A Lost Hole Mr. Meyer was instructed to plug the well as follows:8 5/8" to 1263' circulated w/ cement. 4 1/2" to 5889' cemented.Top perforations 5847' Plug bottom w/ 30 sacks cement.Top of cement 5600' Mud 5600' to 800'Spot 35 sacks cement 800' to 700' Mud 700' to 45' \neq Plug, Halls & 15 sacks cement 45' to 00.

Very truly yours,

Conservation Division Agent