

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 1 1965
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Davis of Anadarko Prod. Co. has this

date requested permission to plug the following described well:

Mr. Davis guarantees payment of the plugging fee.

Operator's full Name: Anadarko Prod. Co.

Complete Address: Box 351 Liberal, Kansas

Lease Name: Morlan Well No. A-1

Location: C NE SW Sec. 21 Twp. 33S Rge. 34 (E) (W)

County Seward Total Depth 6303' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Davis was instructed to plug the well as follows:

8 5/8"-1652' Circulated w/cement. 4 1/2"-4293' Cemented. Top perforations 4231'

Plug bottom w/20 S ax. cement top cement 3850' Mud 3850' to 700'

Spotted 35 S ax. cement 700' to 600' Mud 600' to 45'

Plug, 15 S ax. cement 45' to 0'

Very truly yours,

Hugh [Signature]
Conservation Division Agent