

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
245 North Water  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, Kansas 67202

Dear Sir:

Mr. Riggs of Anadarko Prod., Co. has this  
date requested permission to plug the following described well:

Mr. Riggs guarantees payment of the plugging fee.

Operator's full Name: Anadarko Production Co.

Complete Address: Box 351-Liberal, Ks. 67901

Lease Name: Morlan "A" Well No. 5

Location: C NE NE Sec. 21 Twp. 33s Rge. 34 (E)(W) W


County: Seward Total Depth 6385 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Riggs was instructed to plug the well as follows:

1667' 8 5/8" casing w/800 sax cement. Set 50 sax cement plug  
at 1630'-Set 25 sax cement plug at 700'-Bridge at 40' & 10  
sax cement to 5' below Gl. 5 sax in rat hole & 2 sax in  
mouse hole. Cemented by Howco.

Very truly yours,

  
Conservation Division Agent  
Kansas

RECEIVED  
STATE CORPORATION COMMISSION

DEC 19 1979  
CONSERVATION DIVISION  
Kansas