

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 28 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Moddy of Leben has this

date requested permission to plug the following described well:

Mr. Moody guarantees payment of the plugging fee.

Operator's full Name: Leben Oil Corporation

Complete Address: Box 486, Great Bend, Kansas

Lease Name: Etzold Well No. 1

Location: C NE SW Sec. 22 Twp. 33 Rge. 34 XB (W)

County: Seward Total Depth 6494' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Moody was instructed to plug the well as follows:

8 5/8" to 1647' circulated w/ cement. 4 1/2" to 6434' cemented.


Top perforations 6380' Casing Parted at 3600'

Plug bottom w/ 30 sacks cement. Top of cement 2400'

Mud 2400' to 900' Spot 35 sacks cement 900' to 800'

Mud 800' to 450' Plug, HULLS & 15 sacks cement 45' to 0'.

Very truly yours,


Conservation Division Agent